THE UNIVERSITY OF ALBERTA

STRUCTURAL GEOLOGY AND STRATIGRAPHY OF THE COAL-BEARING AND ADJACENT STRATA NEAR MOUNTAIN PARK, ALBERTA

by

© WARD E. KILBY

A THESIS

SUBMITTED TO THE FACULTY OF GRADUATE STUDIES AND RESEARCH

IN PARTIAL FULFILMENT OF THE REQUIREMENTS FOR THE DEGREE

OF MASTER OF SCIENCE

IN

GEOLOGY

DEPARTMENT OF GEOLOGY

EDMONTON, ALBERTA

FALL, 1978

ABSTRACT

In a 140 sq km area of the Nikanassin thrust sheet near Mountain Park, Alberta, over 800 outcrops and 450 borehole logs were examined. Many of the positional, stratigraphic and orientation data thereby accumulated were stored, retrieved and processed using the computer. Computerized techniques were used to plot outcrop maps, establish cylindrical structural domains, calculated fold axes, rotate domains, and construct single and composite down-plunge plots from which structural cross sections and profiles could be drawn.

The coal-bearing Lower Cretaceous Luscar Formation is probably only 340 m thick and contains only four seams thicker than 1 m. The 11 m Kennedy seam has been correlated with seams along 350 km of the Rocky Mountains from Nordegg, Alberta to Mount Belcourt in northeastern British Columbia. The Lower Cretaceous Mountain Park Formation, 200 m thick, can be distinquished from the underlying Luscar on the basis of its consistent green colour, the occurence of conglomerates and its greater resistance to erosion.

Structural mapping and the use of down-plunge projections have led to the recognition of five hither to unrecognized or only incompletely identified thrust faults.

These cut up section to the northeast at angles of about 5° and have displacements of 1 to 2 km. Traced down section to the northwest, these faults appear to represent splays from the McConnell and Miette thrusts. Up section to the southeast they flatten and merge in the Upper Cretaceous Blackstone Formation. Folding in the thrust sheets appears to have resulted from the stepping of thrusts from one stratigraphic horizon to another.

ACKNOWLEDGEMENTS

The author wishes to thank Consolidation Coal Company of Canada for providing access to all their field and borehole data in the study area. Without their cooperation this study would not have been possible. Much of the study was carried out while the author was a graduate teaching assistant in the Department of Geology. National Research Council of Canada and Geological Survey of Canada grants in aid of research to Dr. Henry Charlesworth helped defray certain expenses related to the project. Geologists of Consolidation Coal Company of Canada and Luscar Limited provided information and encouragement with the regional seam correlation. The author also wishes to acknowledge the guidance and encouragement of his supervisor Dr. Charlesworth. Dr. Chris Gold, Mr. Dave Flint and Mr. Bruce Vincent provided invaluable help with computer related problems. Mr. Ron Swaren and Mr. Scott Anderson worked with the author in the field and Miss Kathy Berndt helped digitize map data and verify data files.

TABLE OF CONTENTS

***

LIST OF FIGURES

LIST OF PHOTOGRAPHIC PLATES

INTRODUCTION

Coal occurs at two stratigraphic levels in the Rocky Mountains of west-central Alberta, namely in the Lower Cretaceous Luscar Formation, where it is of metallurgical grade, and as thermal coal in the Brazeau (Saunders or Wapiti) Group of Late Cretaceous to Paleocene age. Little has been published on the structural style of either set of coal measures. The purpose of this study was to determine as much as possible of the macroscopic structure of the older set of coal measures and adjacent strata in a 140 sq km area of the Foothills near the former coal mining community of Mountain Park (Fig. 1). More precisely, the objectives were to (1) produce a detailed geological map and cross section of the area, (2) use computer techniques to store, retrieve and process the available surface and subsurface geological data and (3) examine the Luscar stratigraphic section and its relationship to surrounding areas containing Luscar strata. It was hoped that the study would (a) improve the efficiency of coal exploitation in the Mountain Park area, (b) be a case history of interest to the coal mining industry elsewhere in Alberta and British Columbia, (c) illustrate the ease and power of computer-based numerical techniques in structural analysis, (d) contribute to our knowledge of Rocky Mountain geology.

Mountain Park, about 320 km west of Edmonton, is



Figure 1. Geological map of the Rocky Mountain Foothills between the Athabasca and North Saskatchewan Rivers showing thesis area stippled. (1) McConnell thrust, (2) Miette thrust, (3) Nikanassin-Bighorn thrust, (4) Folding Mountain thrust and (5) Brazeau thrust.

readily accessible by road from Edson and Hinton via Cadomin or from Nordegg by means of the Forestry Trunk and Grave Flats Roads. The Canadian National Railway's Coal Branch at present ends at Cadomin, 13 km north of Mountain Park, although it formerly extended as far as Mountain Park itself. Within the study area there are numerous roads ranging from those suitable for cars to those accessible only to four-wheel drive vehicles. Although the nearest accommodation is at Hinton, 65 km away, there are public campgrounds near the study area on Whitehorse Creek and the Cardinal River.

Elevations range from 1 675 m in the valley floors to in excess of 2 740 m on the bordering peaks of the Rocky Mountain Front Ranges. Local topographic relief is dependent upon rock type: as a rule it is low on the recessive Fernie, Luscar and Blackstone Formations and somewhat greater on the more resistant pre-Jurassic, Nikanassin, Cadomin and Mountain Park Formations.

Elevation controls the type of vegetation found. Pine and spruce montane forests at lower elevations pass upwards into sub-alpine vegetation and finally into alpine tundra. Forest once covered most of the study area. The effects of a forest fire which narrowly missed destroying Mountain Park in 1913 are still recognizable, with bleached stumps and stunted regrowth occupying the razed sections. Disjunct

alpine-tundra species are under study in the area by graduate students from the Department of Botany (see e.g. Mortimer 1978).

The study area lies within the Mountain Park map-sheet which was mapped by the Geological Survey of Canada in 1924 and 1925 (MacKay 1929). No accompanying report was ever published, and the most comprehensive written work on the area is MacKay (1930). Earlier regional studies which embrace the Mountain Park area include those by Dowling (1910,1915), Stewart (1917) and Allan and Rutherford (1924). Recent statigraphic, paleontological and sedimentological studies involving strata within the thesis area include those by Kryczka (1959), Stott (1963,1968,1974), Mellon (1964,1966), Hacquebard and Donaldson (1974), McLean (1977) and Gibson (1978).

The development of the coal mining industry in the Rocky Mountains of west-central Alberta coincided with the construction of the Grand Trunk Pacific and Canadian Northern Railways in the early part of the century. Within the study area John Gregg in 1909 discovered and staked a coal showing "... at the base of a mountain later known as Mount Cheviot ..." (Ross 1974 p. 10), probably along the McLeod River in the immediate vicinity of the old townsite of Mountain Park. By the summer of 1910 Gregg had succeeded in interesting a British company, represented by a mining

engineer called Robert Thornton, in his property. Thornton returned in 1911 to develop a mine on behalf of Mountain Park Collieries. Mining began in 1912 and continued uninterruptedly until 1950 when operations ceased owing to lack of markets. Altogether a total of six million tonne of coal was extracted in the area. The town of Mountain Park has since been dismantled and all that remains are the cemetery, several concrete foundations and the old mine pits with their spoil piles. Some details about the history of the mine and the town are to be found in Ross (1974).

The last decade has witnessed renewed interest in Alberta coal. At the same time there has been increasing concern about the effect that coal mining can have on the environment, and many areas in the Rocky Mountains and Plains cannot at present be exploited for coal as a result of legislation passed by the Government of Alberta. The Mountain Park area, however, lies in Category 4 of the Alberta Coal Development Policy in which "Exploration [and] ...Development [are] permitted under normal approval procedures" (Government of Alberta 1976, p. 18). The ground underlain by coal in the Mountain Park area is leased to a consortium of Consolidation Coal Company of Canada Ltd. and Luscar Ltd. and over the past 10 to 15 years has been geologically investigated by this consortium. During four months in the summer of 1976 the author was hired by Consolidation Coal Company of Canada to map the coal bearing

Luscar Formation and contiguous formations of the area. In addition the author spent about one month mapping the adjacent formations in more detail during his days off and at the end of the field season. Approximately 14 trips to the Red Deer office of the Company were required to interpret and record the subsurface data contained in borehole logs and old mine plans. These trips were made between September and December 1976 while in full time attendance at the University of Alberta.

COLLECTION AND PROCESSING OF STRUCTURAL DATA

Data Collection

Field Data

While in the field, mapping proceeded essentially by visiting outcrops, plotting positions on aerial photographs, determining structure and stratigraphy and entering this information on field data sheets. Certain stratigraphic contacts, for example the boundaries of the Cadomin Formation, were traced on the aerial photographs using topographic features identified both in the field and on stereoscopic pairs of photographs. Data pertaining to the position of each outcrop, the orientation of bedding and the identity of the formation exposed there were transferred as soon as possible to the base map along with the traces of formational boundaries, faults and the axial surfaces of folds. Throughout the study, as understanding of the structure improved, the positions of these traces were continually adjusted.

Transportation was by means of a Ford 3/4 ton 4-wheel drive truck and two Suzuki RV125 motorcycles. This combination of vehicles greatly enhanced the work potential

of the field crew.

Two sets of aerial photographs were used. The first set, prepared by Co-ordinate Aerial Surveys at a scale of 1:14 400, centered on areas underlain by the Luscar Formation. A second set of photographs produced by the Alberta Department of Energy and Natural Resources at a scale of 1:21 120 provided complete coverage. Due to extensive shadows and poor contrast the latter photographs were of inferior quality and used only where absolutely necessary. A scale of 1:10 560, more amenable to field work, was obtained by enlarging the Government photographs by a factor of two.

Topographic maps for the Mountain Park area, produced by Co-ordinate Aerial Surveys, were available at two scales. The more extensive map, covering 85 sq km at a scale of 1:4 800 with 25-foot contours, covers the outcrop of the Luscar and immediately surrounding strata. The other map, covering 10 sq km at a scale of 1:1 200 with 5-foot contours, provides coverage of those areas where mining is anticipated. Beyond the limits of these accurate maps the only available topographic control was from a survey carried out from 1921 to 1924 at a scale of 1:63 360 by the National Topographic Service. The map resulting from this survey (83-C-14) published in 1924 is inaccurate at the scale of the present investigation.

Field sheets enabling all Company geologists to record lithologic and structural data uniformly, precisely and accurately were designed before the field season by the author and the staff of the Consolidation Coal Company of Canada. Although subsequently found to be too general for this study they were nonetheless of considerable benefit (Fig. 2). For structural studies the following changes to the field sheets are recommended:

1) More space be provided for orientation measurements: data entered in the existing space required extra documentation to avoid later confusion.
2) Less space be provided for folds, joints and faults: data pertaining to these structures are better recorded elsewhere, with only the fact that they are absent or present recorded on the field sheet.
3) Less space be provided for lithologic information: although undoubtedly excellent for a lithologically oriented study this section was rarely used.

Data collection and recording at the outcrop form the basis of geologic mapping and are possibly the most common source of errors in a mapping project. Therefore a system of accurate and concise collection and recording is of the utmost importance. The system used in this study was as follows.


PROPERTY ________ OUTCROP No. ______
GEOL. ______ DATE ______ AIR PHOTO ______
FIELD PHOTOS: PLRD. ______ 110 ______ 35 ______
OUTCROP TYPE ... O/C TRENCH | EXTENT(m) L.___ W.___ Thk.
BEDDING _/_ _/_ _/_ _/_ _/_ _/_
FORMATIONS EXPOSED -
FOLDS YES NO: INTENSITY LOW. MOD. SVR. / TYPE SYM. ASYM. SYN. ANCL. / AXIAL PLANE _/_ _/_ _/_ / FOLD AXIS _/_ _/_ _/_
JOINTS YES NO: ORIENT _/_ _/_ _/_ / DENSITY __/ft. __/ft. __/ft / FILLING _/_ _/_ _/_
FAULTS YES NO: TYPE CNTR. EXT. LAT. IDRM. / ORIENT _/_ _/_ _/_ / SLICK _/_ _/_ _/_ / SENSE HWUP HWDN RL. L.L.
FOSSILS: YES NO / TYPE ______ / SMPL. ______
ADDITIONAL PAGES YES NO NO. ______
COMMENTS:

MAJOR LITHO % of O/C
TYPE Clst. Slst. Sdst. Cngl. Coal CO_3
MODIFIER Shly. Slty. Sndy. Pbbl. Carb. Calc.
GRAIN SIZE vf f m crs vcr pbbl.
COLOR Fresh Wthr.
SORTING Poor Mod. Well | WTHR. NAT. Recess. Mod. Resist.
BEDS(in.) .1 .1-.4 .4-1 1-4 4-12 12-36 36
SED. STRUC. X-bdg. Grdd. Bdg. Cntd. Bdg. Cast Rpmk. Other

Minor Litho. % of O/C — TOP MIDDLE BOTTOM DISP.
TYPE Clst. Slst. Sdst. Cngl. Coal CO_3
MODIFIER Shly. Slty. Sndy. Pbbl. Carb. Calc.
GRAIN SIZE vf f m crs vcr pbbl.
COLOR Fresh Wthr.
SORTING Poor Mod. Well | WTHR. NAT. Recess. Mod. Resist.
BEDS(in.) .1 .1-.4 .4-1 1-4 4-12 12-36 36
SED. STRUC. X-bdg. Grdd. Bdg. Cntd. Bdg. Cast Rpmk. Other

Minor Litho. % of O/C — TOP MIDDLE BOTTOM DISP.
TYPE Clst. Slst. Sdst. Cngl. Coal CO_3
MODIFIER Shly. Slty. Sndy. Pbbl. Carb. Calc.
GRAIN SIZE vf f m crs vcr pbbl.
COLOR Fresh Wthr.
SORTING Poor Mod. Well | WTHR. NAT. Recess. Mod. Resist.
BEDS(in.) .1 .1-.4 .4-1 1-4 4-12 12-36 36
SED. STRUC. X-bdg. Grdd. Bdg. Cntd. Bdg. Cast Rpmk. Other

Figure 2. Field data sheet with the front shown on the left and the back on the right (original size 10x17 cm).

1) The position of the station or outcrop was recorded on the aerial photograph and a note on the accuracy of this position placed in the field notes. A small pin hole through the photograph with the appropriate label on the back provided a permanent record of the position.

2) A short lithologic description, the formation name and the reasons for assigning the strata to the formation were recorded.

3) Bedding plane orientations were measured and recorded in

degrees as dip direction and dip. Dip direction, the azimuth of the direction normal to the strike in which the strata young, can range from 0 to 359°. Dip, the angle through which the strata have apparently been rotated, can range from 0 to 180°, being greater than 90° in the case of overturned beds. The recording of orientations in the field and in all subsequent work is represented as dip direction/dip or trend/plunge for planar and linear orientations respectively. Provided no mesoscopic folding was observed at the outcrop, five bedding plane orientations were measured within 3 m of the position recorded above. When mesoscopic folding was present five or more orientations were recorded, if necessary beyond the above 3 m limit. At several outcrops two sets of measurements were recorded separately, one pertaining to mesoscopically folded and the other to uniformly oriented strata. Two types of compass were used to measure orientations. The Brunton Compass used during the first half of the field season was later replaced by a Freiberger Structural Compass. The latter was preferred for a number of reasons: (1) dip direction and dip are read directly, (2) awkwardly placed surfaces are more easily measured and (3) measurements are collected more quickly. As well as bedding, other structures such as joints, faults and slickensides were recorded in a similar manner.

4) The outcrop was sketched or photographed if warranted. A

Polaroid Land, 110 Instamatic and 135 single lens reflex camera were used to photograph significant views and outcrops. Polaroid pictures reduced the need tc sketch outcrops.

5) The setting of the outcrop and how it fitted into the larger structural picture were briefly described.

Borehole Data

Subsurface data from 350 boreholes were available in the form of driller's, natural gamma and resistivity logs. Various combinations of these logs were available to the author. Characteristic traces of certain coal seams provided excellent marker horizons throughout the area (Fig. 3). Upon familiarization with the traces of specific horizons it was a relatively simple matter to record the down hole distance and from it and the borehole orientations to calculate the coordinates of each horizon intersection. Because the purpose of the boreholes was to determine the position of the Kennedy coal seam in the Luscar Formation, the borehole data are restricted to that part of the section immediately above and below this seam.



Figure 3. Representative borehole geophysical logs. The natural gamma logs are on the left and resistivity on the right. The positions of these holes are give
mark the top and bottom of the seam and of a sandstone parting in the seam. Hole numbers followed by L of U are holes in which the Kennedy seam was duplicated b



. The positions of these holes are given in Figure 9. The correlation lines
which the Kennedy seam was duplicated by a major fault.

Mine Data

Subsurface information was available not only from boreholes but also from mine plans of the old underground workings whose distribution is shown in Figure 4. Four kinds of information were found to be particularly useful; (1) Surveyed elevations allowed the (x,y,z) coordinates of about 100 points on the Kennedy seam to be determined and subsequently placed in the computer file MPMW. By comparing the mine entries on the plans with the scars that these entries have left on the ground, these coordinates were adjusted to the map values. (2) Orientations of bedding were noted at about 25 locations. (3) The hanging wall intersections of the Kennedy and Michelin seams with the Drummond Creek thrust were positioned from the eastern limits of mining (Fig. 4). (4) The orientations of the haulageways gave the approximate strike of the Kennedy and Michelin seams.

Data Storage

One of the major objectives of the present study was to use the computer as much as possible to store, retrieve and process structural data. The data involved in these procedures were mainly: (a) coordinates of outcrops, (b) points on the Kennedy seam in boreholes and old mine



Figure 4. Horizontal extent of underground mine workings at Mountain Park.

workings, (c) orientations of bedding, (d) identifications of formations and horizons, (e) data sources and (f) confidence parameters. These data, which come from (1) outcrops, (2) boreholes, (3) subsurface mine workings and (4) an open pit referred to below as the East Pit were placed in five separate files: (a) O/C and MP.AXIS, (b) MPDH, (c) MPMW and (d) MPEP. The files O/C, MP.AXIS and MPEP contain orientation and stratigraphic data obtained from outcrop measurements. Data from the 900 outcrops containing uniformly oriented strata were recorded in O/C whereas data from the 25 outcrops with mesoscopic folds were stored in MP.AXIS. Data collected from 50 stations in the East Pit were stored in MPEP. MPDH contains positional data on the Kennedy seam in 300 boreholes whereas MPMW contains orientation and positional data from the Kennedy seam recorded at 100 locations from plans of the old mine workings. All files were constructed after the end of the field season.

Approximately 900 outcrops were examined during the course of the field season and located on the 1:4 800 and 1:63 360 base maps. Transfer of locations from aerial photographs to the maps were made using relationships to nearby features identifiable on both the map and aerial photographs. Those outcrops that could not be satisfactorily transferred in this manner were accurately positioned using the Bausch and Lomb "Zoom Transfer Scope" at the end of the

field season. The error in the position of an outcrop as positioned on the map depended on the accuracy of (1) its position on the aerial photograph, (2) the transfer from photograph to map and (3) the maps themselves. The first source of error is unlikely to be more than 3 m although in a few cases, due to shadows or the featureless nature of the terrain, the difference could be as much as 10 m. The second and third sources cf error combined are probably less than 10 m but could be as much as 100 m in the case of the 1:63 360 map. Computerization of the outcrop information required first that the x, y and z coordinates for each station be calculated and recorded. The grid system used was the same as that used during the early mining activity in the area. The origin is at 52.923630 latitude and 117.269730 longitude and the grid, which is measured in feet, is parallel to the Dominion Land Survey. The axes for these coordinates were due east (x), due north (y) and vertically upwards (z). Personnel from the Computing Services Department used a digitizing system described by Perry and Butler (1970) to determine the x and y coordinates directly from the base maps and to place these coordinates along with the corresponding station numbers directly onto magnetic tape. The error associated with this procedure is probably insignificant compared with the errors referred to above. Elevations determined by interpolation between contours were subsequently added to the x and y coordinates on tape. The error in a z coordinate is likely to be one order cf

magnitude less than the error in the associated x and y coordinates. This procedure was used for all coordinates in files O/C and MP.AXIS. Coordinates used in MPDH and MPEP were calculated from their respective surveys. Borehole collars had been surveyed by professional surveyors whereas the East Pit stations were surveyed and plane tabled by the author. Errors associated with these surveys are probably less than 1 m. Errors associated with positioning borehole intersections due to hole deviation are believed to be minimal due to (1) the shallowness of the boreholes which average 90 m in length, and (2) the large angles, rarely less than 60°, between the strata and the boreholes, most of which were drilled vertically. Coordinates for the MPMW file were obtained by direct measurement from the mine plans. These positions are likely accurate to within 5 m.

Data descriptions, formats and partial listings of O/C, MPDH, MPMW, MPEP and MP.AXIS are located in Appendix 1.

Data files were constructed without any prior knowledge of the format mcst likely to satisfy the needs of this study. To determine the most convenient format several were used in the hope that one would prove easier to handle. The following conclusions were drawn as a result of this experimentation.

1) Whenever possible numeric rather than alphabetic codes should be used. Although alphabetic characters are

ordered and can be compared, they are more difficult to manipulate.

2) Integers should be used in place of real numbers whenever possible. Integers are easier to manage and provide a more readable printout.

3) Columns of numbers in the file should be separated by spaces, thereby producing a more readable file.

4) A counter specifying the number of orientation measurements at each station should be included. This simplifies programming and cancels the need for an initial counting step in each subsequent program.

5) Although the notation of northings followed by eastings is widely used by surveyors, that of eastings followed by northings is preferred because all computer programs used by the author to process data accept coordinates with this sequence.

6) Dip direction and dip readings should be recorded in integrated rather than segregated format because the processing computer programs accept data with this format.

Data Retrieval

Structural analysis in the study area was carried out in a domain by domain fashion, the data from each domain

being processed using several Fortran programs. Before processing could occur, however, the relevant data had to be retrieved from the original file or files, reformatted and placed in a new file. Several Fortran programs were developed to extract the required data from the appropriate file and place them in an Analysis Ready (AR) file whose format is compatible with the processing programs. Outcrop data from the O/C file were obtained by specifying the required outcrop numbers and running the program STATION. Borehole and mine workings data pertaining to the Kennedy seam were retrieved by specifying north-south and east-west limits and running the programs COALADD and COALADD1, respectively. These three types of data were then combined into a single AR-file whose first and last lines were added using the system's EDIT routine. Similar programs written to retrieve data concerning joints, fold axis orientations and surface positions of boreholes were used too rarely to warrant further description here. A detailed description of the contents and format of the AR-file, listings of STATION, COALADD, COALADD1 and a sample retrieval are given in Appendix 2.

Data Processing

Definition of structure and stratigraphy in an area underlain by coal-bearing strata is of the utmost importance

in any evaluation of its economic potential. A picture of the structure and stratigraphy of the study area began to be built up while the author was still in the field. After the field season had ended, further analysis of the field, borehole and mine workings data led to the progressive refinement of this picture. Much of this analysis was carried out by processing the data using various numerical computer-based techniques on an Amdahl 470V/6 digital computer. These techniques have several advantages over the graphical and qualitative methods normally used. First, graphical and other errors are eliminated; secondly, the techniques are purely objective; thirdly, the results are reproducible and commonly in a form suitable for statistical analysis, fourthly, the results are more quickly produced and are more accurate. Although Charlesworth et al. (1976) and Langenberg et al. (1977) have discussed many of these techniques, the author believes that at this point it would be informative to illustrate just how easy they are to implement.

Means and Mesoscopic Fold axes at Outcrops

The repeated measurements of bedding orientation made at outcrops were processed first to determine (1) the mean orientation in the case of outcrops in the O/C file with uniformly dipping strata and (2) the fold axis in the case of outcrops in the MP.AXIS file with mesoscopically folded

strata. The mean can be estimated by calculating the sum of unit vectors representing the poles to the repeated measurements. Alternatively it can be found by calculating the eigenvector associated with the maximum eigenvalue of a 3x3 matrix of summed direction cosines of these poles. The fold axis can be found from the eigenvector associated with the minimum eigenvalue of the same matrix (see below).

The Fortran programs MEANS, available in the Department of Geology, and EIGMEAN, listed in Appendix 3(a), can both be used to calculate the mean and fold axis in the cases of uniformly oriented and folded strata, respectively. Whereas EIGMEAN was used to obtain the mean bedding orientations, MEANS calculates the concentration parameter which measures the dispersion of the repeated measurements about the mean (Mardia 1972, p. 251) and was used to test the cylindricity of folding (see p. 25). EIGMEAN also enabled the axes of the mesoscopic folds to be calculated.

Establishment of Potential Domains

Since structural analysis proceeded on a domain by domain basis, the first step was to divide the area into potential domains within which, by inspection, folding appeared to be cylindrical (Fig. 5). The various steps that must be carried out in the analysis of a typical potential domain are listed in Figure 6. Once the limits of a



Figure 5. Domain boundaries and fold axes.



Figure 6. Retrieval and cylindricity testing procedure. Z being the number of runs required to define fold axis.

potential domain had been selected the Fortran programs STATION, COALADD and COALADD1 were used to retrieve appropriate outcrop and Kennedy seam subsurface data and place them in an AR-file. Once the AR-file for the potential domain had been constructed the data in it could be subjected to all the analytical procedures described below.

Macroscopic Fold axes

The most important structural element calculated in a potential domain was the fold axis. This orientation was used in the (a) quantitative description of folding, (b) preparation of down-plunge projections and (c) determination of the displacement along faults and the angle between faults and bedding. Thus it was important to estimate the fold axis as precisely as possible. The fold axis was estimated using a method similar to that described above for mesoscopic folds except that the input consisted of the mean orientations of bedding at the various outcrops stored in the file O/C rather than the original field measurements of bedding stored in the file MP.AXIS. Another method for estimating the fold axis that uses down-plunge projections will be discussed on page 30.

Testing Cylindricity

The eigenvector associated with the minimum eigenvalue (minimum eigenvector) of the 3x3 matrix of summed direction cosines gives the fold axis only if folding in the area is cylindrical. Thus the potential domain had to be examined with a view to establishing that it was indeed a domain within which folding could be considered cylindrical. In an ideal cylindrical fold where all the s-poles lie in a plane normal to the fold axis, the minimum eigenvalue, λ_3, is zero. Although some departure from this ideal situation is permitted to allow for measurement errors, bedding-plane roughness and small-scale incongruent folding, clearly should be small: just how small will be discussed below. In addition, a cylindrical fold should have a wide spread of s-poles in the plane normal to the fold axis. A uniform spread yields maximum, λ_1, and intermediate, λ_2, eigenvalues that are almost equal; clearly here the eigenvector associated with λ_3 can, as long as the latter is small enough, be taken to give the fold axis. This is in marked contrast to the situation where the s-surfaces in an area are homoclinal and where λ_1 is large and λ_2 and λ_3 are small and approximately equal to one another: here the fact that λ_3 is small does not mean that the associated eigenvector can be taken to give the fold axis. Obviously, however, there are many situations between the two extremes referred to above where the minimum eigenvector can be assumed to give the fold

axis. As long as λ_3 is small and at least one order of magnitude less than λ_2 and as long as λ_1 is within one order of magnitude of λ_2, the minimum eigenvector can reasonably be assumed to give the fold axis.

Charlesworth et al. (1976, pp. 55-56) discussed the measurement of s-pole scatter about the plane normal to the fold axis. Following them, since λ_3 is the sum of $\cos^2\phi_i$ where ϕ_i is the angle between the fold axis and the ith of p s-poles, the variance and standard deviation of $\cos\phi_i$ are given by λ_3/p and the square root of this quantity, respectively. Another measurement of scatter about the plane normal to the fold axis, known as the standard scattering angle, is given by the arcsine of the standard deviation referred to above. One approach put forward by Charlesworth et al. (1976, pp. 55-56) to determine how much scatter is permissible in a cylindrical fold used a chi-square test to compare the variance at the scale of an outcrop, measured by the pooled estimate K of the concentration parameters of the repeated measurements at the outcrops, with the variance in the whole area, measured by λ_3. The null hypothesis of cylindricity was rejected if the product of K and λ_3 was greater than the appropriate value of chi-square. Another approach compared the variance in the area as a whole with that in two halves of the area. Using an F-test, the null hypothesis of cylindricity was rejected if the minimum eigenvalue in the whole area was significantly greater than

the sum of the minimum eigenvalues in the two halves.

The author believes that the above two statistical tests of cylindricity should be regarded only as guides rather than final arbiters in deciding whether or not folding in an area is cylindrical. As discussed above, the relative sizes of the three eigenvalues should be taken into consideration. The absolute value of the standard scattering angle in the potential domain should also be considered along with the difference between the orientations of the fold axes in its two halves. Thus the author believes that, standard scattering angles and differences between fold axes of more than 10° and less than 2° can be regarded as sufficient grounds for rejecting and accepting cylindricity, respectively. In spite of the quantitative nature of the above criteria, the final decision concerning the acceptability of an area as a domain within which folding can be considered cylindrical will depend amongst other things on the nature of the study and on the use tc which the fold axis orientation will be put.

The programs CYLTEST and EIGEN already available in the Department of Geclogy were both used to determine the eigenvalues and associated eigenvectors of the 3x3 symmetrical matrix of summed direction cosines. CYLTEST, which accepts an AR-file as input, also calculates the standard deviaticn referred to above and expresses the

departure of each bedding-pole from the plane normal to the minimum eigenvector in terms of this standard deviation. This information was extremely useful in detecting apparently erroneous readings and in drawing the boundaries between domains. The program EIGEN accepts an AR-file as input only if it has previously been operated on by the programs STEREO and FINPUT. STEREO, which is described in Appendix 3(b), removes all but the orientation data from the analysis file and FINPUT, already available in the Department of Geology, transforms these data into direction cosines. The STEREO-FINPUT-EIGEN procedure was quicker than CYLTEST in that it was more readily performed on many areas at once. Appendix 3(c) contains a detailed statistical investigation of the cylindricity of the East Pit study area following the proceedures outlined in Figure 6.

Structural Cross sections and Profiles

Cross sections used by the coal industry to calculate reserves are conventionally constructed by taking the coal seam outcrops and borehole intersections immediately adjacent to the line of section and projecting them parallel to the strike. This procedure leaves much to be desired for the following reasons; (1) data some distance away from the line of section are not used, (2) orientational data from outcrops that are stratigraphically adjacent to the coal seam are not used, (3) in the case of a coal seam involved

in folds with a moderately to steeply plunging axis, the structural configuration of the seam will be distorted by projecting points parallel to the strike instead of the fold axis.

Cross sections of deformed sedimentary rocks used to illustrate their macroscopic structure are generally constructed to be consistent with outcrop and subsurface data along the line of section and to show the competent stratigraphic units as having maintained their original thicknesses and as having experienced the same shortening parallel to layering. Such "balanced" cross sections do not consider the significant but variable mesoscopic shortening parallel to and thickening normal to layering that affects even the most competent units in the Rocky Mountain Foothills.

Cross sections used to calculate reserves or to illustrate structure may be constructed more accurately and objectively by projecting outcrop and subsurface data over considerable distances parallel to the fold axis onto a plane of section that is either normal or oblique to the fold axis. Such projections can be carried out using the Fortran program SECT5, available in the Department of Geology, which uses an AR-file as input. Where orientation data are available the program calculates the pitch of bedding on the plane of the section. The projection is then

constructed by the Calcomp Plotter. The run commands, input, output and resultant plot are given in Appendix 3(d).

Where orientation data were scarce, the method described on page 25 for estimating the fold axis could not be used. As long as sufficient positional data on one stratigraphic horizon are available (for example data provided by boreholes) the above method for constructing down-plunge plots can be used to estimate the fold axis. Various plots are obtained, each associated with its own projection direction. The direction that gives the least scatter of the projected points about a line can be taken to be the fold axis. If a cathode-ray tube terminal is used, a plot can be obtained in a few minutes instead of a few hours as is the case of the Calcomp Plotter, thereby enabling the fold axis for a set of data points to be determined on a trial and error basis within half an hour.

The Fortran program DOMROT, available in the Department of Geology, was used to rotate the orientational and positional data in a domain so that its fold axis became parallel to that in an adjacent domain. Each rotation took place about an origin on the boundary between the two domains involved and about an axis normal to the plane containing the two fold axes. The reason for carrying out such rotations was to enable a single profile to be constructed for areas with varying fold axes. An example of

the run commands, input and output for this program is given in Appendix 3(e).

Constructing composite profiles or cross sections of two or three domains is straightforward but where more domains are involved the various rotations should be carried out in a certain order to ensure that discontinuities do not develop between domains. In this study the domains to be rotated tended to occur in elongate strips one or two domains across and up to five domains long. The method followed in carrying out rotations and in constructing cross sections is illustrated in Figure 7.

Map Construction

Maps showing bedding orientations at outcrops were readily constructed by the Calcomp Plotter using subroutines BOUND and MAP listed in Appendix 3(f). A short program incorporating these two subroutines was used to construct maps of varying scales for areas the size of one domain to the size of the study area (see e.g. Fig. 13). Appendix 3(f) contains an outcrop map of the East Pit as well as the program and run commands used in its preparation.



Figure 7. Domains along section line D-D' before and after rotation.

Orientation Diagrams

Orientation diagrams are very useful in gaining a visual appreciation of orientations in domains and can be prepared with the aid of plots produced by the computer. The plots, which have to be contoured manually, were produced by running the Fortran programs STEREO, FINPUT and PLCT with an AR-file as input. Appendix 3(g) illustrates the construction of an orientation plot for Domain 1.

Thickness Determination

The absence of continuous exposures from most of the study area meant that stratigraphic thicknesses had to be determined indirectly rather than by direct measurement. Each determination involved finding the coordinates of two points, one on the upper, one on the lower bounding surface of the interval in question, and estimating the orientation of the intervening strata. Where the strata are uniformly oriented the thickness can be shown to equal the vector product

$$(x_1 - x_2, y_1 - y_2, z_1 - z_2) \times l, m, n$$

where $[X_1, Y_1, Z_1]$ and $[X_2, Y_2, Z_2]$ are the coordinates of the two points and [l,m,n] the direction cosines, referred to the same axes, of the normal to bedding. When the strata have been folded on a scale larger than the distance between the two points, i.e. where the orientation varies

progressively across the interval, and where folding is parallel in style, a method similar to that developed by Busk (1929, p.14) was used except that the thicknesses were determined numerically on a plane normal to the fold axis. Thicknesses were calculated using the APL program THICK. A listing of this program together with two sample runs are given in Appendix 3(h).

There were two sources of error in the repetitive thickness calculations: (1) deformation within the measured interval is present in the form of thrusting or small scale folding, instead of being non-existent or such that the orientation of bedding varies progressively from one bounding surface to the other, (2) the dip of the strata within the interval or the coordinates of the two points were incorrectly estimated. Whereas errors of the second type lead either to under- or over-estimations of thicknesses, those of the first type invariably result in the thickness being overestimated. For this reason, after values more than one or two standard deviations from the mean had been excluded, the thickness of an interval was taken to be about midway between the mean and the smallest individual measurement.

STRATIGRAPHY

Strata ranging in age from Devonian to Late Cretaceous crop out in the Mountain Park area. However, because the objective of the study was to examine the structure of the coal-bearing and adjacent strata, only the following map-units were established:

	Wapiabi Formation
	Cardium Formation
	Blackstone Formation
CRETACEOUS	Mountain Park Formation
	Luscar Formation
	Cadomin Formation
	Nikanassin Formation
JURASSIC	Fernie Group
PRE-JURASSIC	Undivided

Pre-Jurassic (undivided)

The pre-Jurassic strata belong to the Devonian Fairholme Group and Palliser Formation, Mississippian Banff Formation and Rundle Group and the Triassic Sulphur Mountain and Whitehorse Formations. These strata consist largely of carbonates and appear to have behaved as a single competent unit with little internal deformation (Plate 1). The Triassic Whitehorse Formation, the uppermost unit of this

succession is disconformably overlain by the Fernie Group. A section through the Whitehorse Formation along Drummond Creek is given by Best (1966, p. 63).



Plate 1. Structural terrace in the pre-Jurassic unit, Nikanassin Range east of the junction of Whitehorse Creek and McLeod River.

Fernie Group

The Jurassic Fernie Group consists dominantly of black marine shale with thin bands of sandstone and carbonate. A poorly exposed recessive unit with considerable internal deformation (Plate 2), its thickness was impossible to determine accurately but the 300 m quoted by Frebold (1957, p. 90) for the section along the McLeod River serves as a reasonable maximum value. Whereas the lower boundary is

sharp and distinct, the upper contact with the Nikanassin Formation is gradational over approximately 10 m.



Plate 2. Mesoscopically deformed strata belonging to the Fernie Group along Drummond Creek.

Nikanassin Formation

The Nikanassin Formation of Late Jurassic and Early Cretaceous age consists of about 425 m of medium to thinly bedded sandstone, shale and coaly shale of marine and non-marine origin. Although less recessive and better exposed than the Fernie Group, its precise thickness is difficult to estimate because of internal deformation (Plate 3). MacKay (1930, Fig. 4) suggested a thickness of 480 m whereas Kryczka (1959, p. 10), who measured a continous section 386 m thick along MacKenzie Creek, gave 425 m as the

Plate 3. Mesoscopically deformed strata belonging to the Nikanassin Formation along McLeod River.

thickness. Recently, Gibson (1978, p. 380) suggested a thickness of 488 m obtained from measurements along MacKenzie Creek.

Cadomin Formation

The Lower Cretaceous Cadomin Formation unconformably overlies the Nikanassin Formation (Warren and Stelck 1958), although the angularity of the unconformity is probably no more than a few degrees. Only 8 m thick (McLean 1977, p. 798), the formation is largely conglomerate with some thin sandstone lenses. It is extremely resistant and where present usually crops out or forms a ridge. This and its distinctive lithology make it an ideal marker horizon (Plate 4).



Plate 4. Nikanassin (N), Cadomin (C) and Luscar (L) Formation along Drummond Creek. Note the Thornton Creek syncline (S) and duplications of the Cadomin Formation by the Drummond Creek thrusts (T).

Luscar Formation

The Lower Cretaceous Luscar Formation bears metallurgical quality coal in the Foothills of west central Alberta. It consists of about 340 m of essentially non-marine sandstone, siltstone, shale and coal (Fig. 8).

Lithologic differences have been noted between the lower and upper portions of the Luscar Formaticn south of the Athabasca River (Douglas 1956, p. 20; Holter and Mellon 1972, p. 129). Similar differences were found in the study area with the lower part containing thinly bedded siliceous sandstones, shales and shaly coals and the upper part thickly bedded kaolinitic and chloritic sandstones and medium to thick coal seams. North of Cadomin the boundary between these two divisions coincides with a band of marine shales equivalent to the Moosebar Formation of northeastern British Columbia. A shale interval containing brackish to marine coquinas that occurs just below the Cheviot coal seam along Cheviot Creek may be an extension of this shale (Plate 5). Due to poor exposure this contact, which is thought to occur about 195 m above the base of the formation, was not detectable elswhere in the study area. The lower 100-125 m of the Luscar Formation are well exposed along Drummond Creek (Plate 4) while typical upper Luscar strata are exposed in and around the West Pit at Mountain Park. The upper boundary of the formation has been placed at the top



Figure 8. Comparison of Luscar sections (a) MacKay 1930 and (b) the author.



Plate 5. Cheviot seam and underlying shales on Cheviot Creek. The white line marks the base of the coal seam.

of the highest coal seam, the Michelin. Above this seam, which extends throughout the study area, the strata are more resistant to erosion, richer in chlorite and are assigned to the Mountain Park Formation.

The Kennedy seam occurs 270 m above the base of the formation and is the only thick seam in the Mountain Park area. This economically important seam is readily recognizable by its borehole log traces (Fig. 3) and is laterally continous throughout the area (Fig. 9). The seam is divisible into upper and lower benches, 10-11 m and 1 m thick, respectively. The sandstone and shale parting between the two benches is seen to thin abruptly across the trace of the Drummond Creek and Upper Drummond Creek thrust fault from 10 m in the hanging wall to 3 m in the footwall. The majority of coal produced in the Mountain Park area came from this seam. The Kennedy seam is exposed in many old



Figure 9. Stucture contour map of the base of the Kennedy seam. Contours for the hanging wall of the Lower Drummond Creek thrust are not shown.



m. Contours for the hanging wall of the Lower Drummond Creek thrust are not shown.

excavations in the west and central parts of the area while two natural exposures occur east of MacKenzie Creek (Plates 6 and 7). A stratigraphic section containing the Kennedy and Thornton seam in the West Pit (Plate 8) is given in

Plate 6. Kennedy seam outcrop 1 km east of MacKenzie Creek. The seam is approximately 9 m thick.

Appendix 5.

The Michelin seam forms the upper boundary of the Luscar Formation. In the central portions of the area where it has been mined a thickness of 1 to 1.5 m is present. The Thornton seam occurs 20 m below the base of the Mountain Park Formation and is approximately 1 m thick. Although never mined, its presence is well defined by borehole evidence and it is laterally quite continuous. The Michelin and Thornton seams are well exposed along the upper tributary to MacKenzie Creek at an outcrop whose coordinates

Plate 7. Outcrop of the Kennedy seam with well developed cleat 2 km east of MacKenzie Creek. Clipboard is 30 cm long.

Plate 8. The West Pit viewed from the east. The Kennedy seam and lower bench are in foreground. The stratigraphic section given in Appendix 5 was measured fom A to A', F marks Drummond thrust and H marks the Kennedy seam in the hanging wall of the Drummond Creek thrust.

are 17 000 east and 3 000 north. The Cheviot seam, approximately 1 m thick, occurs about 195 m above the Cadomin Formation and is not believed ever to have been

mined. It is seen only in a few boreholes in the eastern portion of the area and at one outcrop along Cheviot Creek (Plate 5). Several other thin shaly coal seams occur within 20 m of the base of the Luscar Formation, and other thin seams occur throughout the formation but due to lack of data their precise stratigraphic position and lateral extent are unknown.

Lack of good exposure meant that the thicknesses of various intervals within the Luscar Formation and of the formation itself could not be measured directly. Instead thicknesses were estimated using repetitive measurements determined by applying the numerical techniques described on page 34 in areas where the structure is approximately homoclinal. The various thickness determinations are as follows.

1) Thickness of the interval between the Kennedy and Thornton seams was obtained from data in eighteen boreholes situated throughout the map area. These yielded a mean of 52 m and a standard deviaticn of 6.6 m. After removing four anomalous values a mean of 52.7 m and a standard deviation of 3.3 m were obtained. The smallest of the remaining 14 values was 48.7 m so the thickness of this interval has been taken to be 51 m.

2) Thickness of the interval between the Michelin and Thornton seams, determined from eight borehole

measurements east of the McLeod River, gave a mean thickness and standard deviation of 25.3 m and 13.2 m, respectively. The removal of two anomalous values changed the mean to 20 m and the standard deviation to 2 m. Of the six remaining values 18 m was the minimum so an interval thickness has been set at 19 m.

3) Thickness of the interval between the Kennedy seam and the Mountain Park Formation, which equals the sum of the above two thicknesses, was also obtained by repetitive calculations based on the old mine plans. Four determinations yielded a mean and standard deviation of 75 m and 9.5 m, respectively. The minimum value was 66 m, which suggests a thickness of about 71 m for this interval. This value is in good agreement with the sum of thickness determinations 1 and 2 (70 m).

4) The interval between the Cadomin Formation and the Kennedy seam has the least intermediate control and being the thickest is the most important in establishing the total thickness of the formation. Repetitive calculations from map positions between McLeod River and Prospect Creek yield a minimum thickness of 260 m with a mean and standard deviation of 278 m and 19 m, respectively. A value of 269 m has been accepted as being the best estimate of the true thickness.

5) Only one borehole intersection of the Cheviot seam could be stratigraphically positioned. The outcrop along Cheviot Creek was of no value in locating the seam

stratigraphically due to structural complexities. In the borehole, located east of McLeod River, the seam occurs 73 m below the Kennedy seam.

The total thickness of the Luscar Formation (340 m) and the distribution of coal seams within it described above differ considerably from those given by MacKay (1930, Fig. 5) who derived his information from the active mine workings. MacKay proposed that the formation is 485 m thick and contains 11 seams (Fig. 8). The author is convinced that the discrepancy between his and MacKay's figures is caused by (1) MacKay's failure to observe several large thrusts in the mine workings and (2) the author's positioning of the boundary with the Mountain Park Formation at the top of the Thornton seam which MacKay considered to be well within the Luscar Formation. By comparing borehole logs, it can be shown that several of MacKay's seams are one and the same. The Kennedy and #3 seams of MacKay both appear to be equivalent to the author's Kennedy seam in the hanging wall of the Upper Drummond Creek thrust and footwall of the Drummond Creek thrust, and very likely his #5 seam is the Kennedy seam in the McLeod River thrust sheet.

Through the use of borehole logs, the Kennedy seam was found to be laterally continuous throughout the Mountain Park area. The presence of a thick and laterally extensive coal seam in the study area and similar occurrences nearby

at Cadomin and Luscar initiated an attempt to correlate the seams and sections in these two areas with those at Mountain Park. Through a literature search and consultation with several coal companies surprising similarities in the Luscar and equivalent coal-bearing strata of the Foothills from the Saskatchewan River in the south to Mount Belcourt in the north were found (Figs. 10 and 11). Correlations were based on (1) height above the Cadomin Formation of the major seam in each section, (2) stratigraphic position and thickness of other seams within the section, (3) stratigraphic position of the Moosebar Formation and the equivalent marine shales within the Luscar Formation, (4) similarities in borehole log traces of seams and surrounding strata (Fig. 12).

Several published sections through the Luscar Formation are not readily correlatable with those shown in Figure 10. The author feels that this may result from the failure on the part of the compilers of these sections to recognize structural complexities such as those seen at Mountain Park. Also local depositional peculiarities may complicate correlation.



Figure 10. A comparison of Luscar sections from Nordegg, Alberta to Mount Belcourt, British Columbia. The locations of these sections are shown in Figure 11.

(1) Nordegg; Consolidation Coal 1976
(2) Muskiki Lake; Luscar Ltd. 1977
(3) Mountain Park; author
(4) Cadomin; Mellon 1967
(5) Luscar; Luscar Ltd. 1977
(6) Thoreau Creek; MacKay 1930
(7) Muskeg River; MacKay 1930
(8) Smoky River; Wrightson 1978
(9) Torrens River; Consolidation Coal 1977
(10) Mount Belcourt; Stott 1968



Figure 11. Locations of sections in Figure 10.



Figure 12. Comparison of borehole geophysical logs from Mountain Park, Luscar and Smoky River.

Mountain Park Formation

The Lower Cretaceous Mountain Park Formation consists of about 200 m of non-marine olive-green sandstones and shales with local black chert pebble conglomerate lenses present near the base. Plant remains and well preserved fossil wood are common. The resistant nature of the thick sandstones of this formation produces prominent ridges throughout the area (Plate 9). The placing of the lower

Plate 9. Looking west across Mountain Park from the Cardium ridge. The West Pit is in the center with the Cadomin and Mountain Park ridges to the north and south, respectively. recessive Blackstone strata underlie the ground south of the Mountain Park Formation.

boundary of the formation at the top of the Michelin seam, located well within the Luscar of MacKay, has increased the thickness of the formation by at least 76 m from the 120 m suggested by MacKay (1930, Fig. 4) and provided a more

mappable boundary. No complete well-exposed section is present in the area but a composite type section could be constructed from outcrops along MacKenzie Creek. The Mountain Park Formation is disconformably overlain by the Blackstone Formation (Stott 1963, p. 25).

Blackstone Formation

The Upper Cretaceous marine Blackstone Formation is composed of recessive dark-grey to black shales, siltstones and rare fine grained sandstones (see e.g. Stott 1966). Due to poor exposure no reliable thickness determinations were made and Stott's (1963, Fig. 15a) thickness of 430 m has been accepted. The formation is conformably overlain by the Cardium Formation.

Plate 10. Looking west along the Cardium Formation. Note Cardium strata in the core of Thornton Creek syncline at the base of Cheviot Mountain in the center of photograph.

Cardium Formation

The Upper Cretaceous Cardium Formation, referred to as the Bighorn Formation by MacKay (1929, p. 474) is a dominantly marine unit of thickly interbedded sandstones and shales. The formation is 75 m thick (Stott 1963, Fig. 16a), extremely resistant and forms a prominent ridge along the southern boundary of the study area (Plate 10).

Wapiabi Formation

Black marine shales of the Upper Cretaceous Wapiabi Formation are present only in the southern portion of the study area.

STRUCTURE

Strata near Mountain Park are disrupted by several thrust faults that generally cut up section to the northeast at low angles. Although both the thrusts and the faulted strata have an overall dip to the southwest, folds are common. Some folds are restricted to individual thrust sheets whereas others are more extensive (Fig. 13, in pocket). The area has been divided for descriptive purposes into five structural units separated by four major thrust faults (Fig. 5).

The area is also divisible into 32 domains within which folding can be considered cylindrical (Fig. 5). Whereas some domains straddle the boundary between two structural units, most are confined to a single unit. Each domain satisfies the test of cylindricity described on page 25. A structural profile for each domain was constructed with the aid of a computer constructed plot showing the projections of data stations parallel to the fold axis onto the plane of the profile and where possible the traces of bedding (Appendix 4). By rotating adjacent domains so that their fold axes coincide, five composite vertical cross sections were constructed and combined to produce one stacked cross section (Fig. 14).



Figure 14. Stacked vertical cross section for the entire map area, projected onto the B-B' section.

Drummond Creek thrust sheet

The Drummond Creek thrust sheet in the southern part of the map area is bounded above and below by the McConnell and Drummond Creek thrusts. Since these faults generally strike southeasterly and easterly, respectively, the width of the thrust sheet increases eastwards from 0.6 km to 9 km. Exposures belong mainly to the Nikanassin, Cadomin and Luscar Formations in the west and to the Mountain Park and Blackstone Formations in the east.

Drummond Creek thrust

Two thrusts, referred to here as the Lower Drummond Creek and Upper Drummond Creek thrusts are well exposed just east of Drummond Creek in the southeast corner of the map area where Nikanassin and Cadomin strata are thrust over the Luscar in both instances. A short distance to the east the Lower Drummond Creek thrust truncates the Kennedy seam in the footwall. Between Prospect and Thornton Creeks both faults are within the Luscar Formation and are responsible for the triplication of the Kennedy seam indicated by borehole data. A short distance east of the West Pit these two thrust faults merge to form the Drummond Creek thrust. Between Thornton Creek and the McLeod River, as seen on the plans of the old mine workings, the fault truncates the

Kennedy and Michelin seams in the hanging wall before apparently becoming parallel to bedding near the top of the Luscar Formation (Fig. 4); in the same distance the fault cuts up through the Mountain Park Formation in the footwall before apparently becoming parallel to bedding near the base of the Blackstone Formation. Between Harris Mountain and MacKenzie Creek the fault cuts up through the Mountain Park Formation in the hanging wall and enters the Blackstone Formation in which it becomes lost to view. Northwest of Drummond Creek the thrusts enters the Nikanassin Formation and appear to merge with the McConnell thrust.

As seen from their traces on the map and cross section (Figs. 13 and 14), the Drummond Creek thrust and its two branches are approximately parallel to bedding and have obviously been folded. Assuming that (1) the folds in the faults and in bedding have the same fold axis, (2) the thickness of the interval between the Cadomin Formation and the Kennedy seam is 270 m and (3) the points where the faults truncate the Cadomin Formation and the Kennedy seam are as shown on Figure 13, then the average angle that the Lower Drummond Creek fault makes with bedding in the hanging wall between Prospect and Thornton Creeks is 5°. The corresponding angles for the hanging wall and footwall of the Upper Drummond Creek thrust are about 3° and 5°, respectively. Both faults cut up section to the northeast. Support for the first of the above three assumptions, the

only one seriously in doubt, comes from the fact that the thrust to bedding intersection in the hanging wall of the Drummond Creek thrust is approximately parallel to the fold axis in the area of the former mine workings. The orientation of the intersection is readily determined from the mine plans by the position where the Kennedy and Michelin seams are cut off to the east by the fault (Fig. 4). There is no way of knowing whether the bedding to thrust angle remains constant at 3 to 5° or whether the thrusts are stepped.

Using the points of truncation of the Kennedy seam and the base and top of the Mountain Park Formation, the average angles between the Drummond Creek fault and bedding in the hanging wall west and east of the McLeod River are 7° and 5°, respectively. The average angle between the fault and bedding in the Luscar and Mountain Park Formations in the hanging wall is 6°. Using the points of truncation of the Kennedy seam and the base of the Mountain Park Formation in the footwall, the average angle between the fault and bedding in the footwall east of Prospect Creek is 1°.

Fold axis orientations in general do not differ significantly across the trace of the Drummond Creek thrust which suggests not only that the fault is approximately parallel to bedding but that there is no appreciable rotational component to the displacement along it. Assuming

the direction of displacement along the fault to be normal to the fold axis the relative positions of the points in the hanging wall and footwall of the Lower and Upper Drummond Creek thrusts at which the Kennedy seam is truncated gave values for the displacements of 2.75 and 2.06 km respectively. That the displacement along these faults is considerable is substantiated by the abrupt thickening of the parting between the two benches of the Kennedy seam across the traces.

The thrust sheet

Strata within the Drummond Creek thrust sheet have been faulted and folded, in places independently of and in places along with the Drummond Creek thrust and its footwall. Among the folds present in both hanging wall and footwall are the Drummond Creek anticline and syncline between Drummond and Prospect Creeks and the East Pit anticline and syncline between the McLeod River and MacKenzie Creek. These structures are described on page 80. Among the structures confined to the thrust sheet itself are the Thornton Creek syncline, several minor folds on the northeast limb of this syncline and the Syncline thrust.

The Syncline thrust marks the northeastern boundary of a fault zone whose southwestern boundary is the McConnell

thrust. Nikanasssin strata form the hanging wall for the entire exposure length whereas Cadomin and Luscar strata are found in the footwall. The fault has Luscar and Cadomin strata in the footwall along Drummond Creek (Plate 4), Luscar to the south of the Syncline Pit (Plate 11) and Cadomin again at the headwaters of East Prospect Creek

Plate 11. Looking east along Thornton Creek syncline. Note Kennedy seam excavation, Syncline thrust (A) and McConnell thrust (B).

(Plate 12). The fault and the overturned Nikanassin and Fernie strata within the fault zone are approximately parallel at 219/45.

The Thornton Creek syncline is the largest single structure in this unit, containing strata from the Fernie Group to the Wapiabi Formation. An overturned plunging fold, its fold axis and axial plane have orientations of 150/17

Plate 12. Old adit in the overturned Kennedy seam, southwest limb of Thornton Creek syncline. The Cadomin Formation is at A.

and 210/34, respectively. Overturned strata in the narrow southwestern limb of the fold commonly dip at 45° SW whereas the broad upright limb has an overall dip of 30° SW. Plates 4 and 11 give natural, near down-plunge views of the fold at the level of the Cadomin and Kennedy seam along Drummond and Prospect Creeks, respectively.

Two sets of mesoscopic folds were observed in the Drummond Creek thrust sheet, one in the Luscar Formation, defined by mine data, the other by outcrops of Mountain Park strata. The fold axis and axial plane orientations of the former folds are 134/15 and 230/67 whereas the fold axis of the outcrop folds is 133/17. These two sets of folds may be

one and the same as a syncline in the mine workings southwest of the folds apparent in Figures 4 and 9 at -12 000 east and 3 000 north when connected to the outcrop syncline yields a reasonable axial plane orientation of 218/68.

Prospect Creek thrust sheet

The Prospect Creek thrust sheet is wedge-shaped, being 7 km wide along Drummond Creek and terminating in the Blackstone Formation east of MacKenzie Creek where the Drummond Creek and Prospect Creek thrusts merge. It exposes Nikanassin, Cadomin, Mountain Park and Blackstone strata.

Prospect Creek thrust

The Prospect Creek thrust is readily discernible along Prospect Creek through duplication of the Cadomin Conglomerate. Half a kilometer northwest of this creek the fault truncates this formation in the footwall to enter the Nikanassin Formation. Outside the area studied, along Harlequin Creek which parallels Drummond Creek 3.5 km to the northwest, the thrust is apparently situated in the Fernie Group and merges with the McConnell thrust. To the southeast the fault gradually cuts up section, truncating the Cadomin

in the hanging wall and the Kennedy seam in the footwall along Thornton Creek. Just east of the McLeod River, former mine workings and borehole data demonstrate that the thrust divides into two major splays and has undergone folding. These splays reconnect to the east where the fault enters the Blackstone Formation. Beyond MacKenzie Creek the fault is not traceable, but it probably merges with the Drummond Creek thrust since the overlying Cardium Formation remains unfaulted for a distance of 7 km southeast of MacKenzie Creek.

Since the surface trace of the Prospect Creek fault is sub-parallel to the traces of the Cadomin Formation in both the hanging wall and footwall, the fault must be nearly parallel to bedding. Using the points of truncation of the Cadomin, Kennedy seam and Nikanassin Formation the angles between the fault and bedding in the footwall and hanging wall west of the McLeod River were found to be 7° and 6°, respectively. A displacement of about 2 km was calculated using the profile positions of the truncations of the Cadomin Formation in the hanging wall and footwall.

The thrust sheet

Strata within the Prospect Creek thrust sheet have been folded at several localities and one small fault was

observed. The Harris Mountain anticline and syncline, while dominantly in the Harris Creek unit, affect this thrust sheet near Harris Mountain are discussed in more detail on pages 70 to 71. Other structures include the Prospect Creek anticline and syncline, an intervening small fault and fold-pair, the East Pit anticline and syncline and the faults associated with the Harris Mountain horse.

The Prospect Creek anticline is a broad feature with an apical angle of approximately 150°. This inclined plunging fold has a fold axis orientation of 130/10 and while hard to discern from orientations on a map is visible in profile view (Fig. 14 and Plate 4). A small thrust fault located on the north limb of the syncline cuts up section at 30° and displaces the Cadcmin approximately 100 m. A short distance to the north of this fault along Drummond Creek a small overturned anticline-syncline pair deforms the Cadomin (Plate 4). These three structures are not recognized to the east and are believed to die out in a short distance. The Prospect Creek Syncline is well defined, fclding Nikanassin, Cadomin and Luscar strata of the Prospect Creek thrust sheet as well as strata cf the Drummond Creek thrust sheet as high as the Blackstone Formation. This fold is upright-plunging with a fold axis orientation of 130/10.

Between Prospect Creek and the McLeod River strata of the Prospect Creek thrust sheet form a homocline with a mean

orientation of 200/30 (Plate 9).

East of the McLeod River the East Pit anticline and syncline are exposed in the East Pit. These folds which terminate to the northwest against the Prospect Creek thrust affect strata as high as the Blackstone in the overlying Drummond Creek thrust sheet. Orientations of 135/10 for the fold axis and 220/67 for the axial plane were obtained from the mine workings, both surface and underground. A detailed description of the East Pit is given on page 80.

A large complex horse containing the Kennedy seam has been defined by drilling north of the East Pit (Fig. 15). The Prospect Creek thrust which underlies the horse has a displacement of about 1.4 km and cuts up section to the northeast at approximately 3° in both the hanging and footwall. The uppermost splay has a displacement of approximately 0.6 km with a mean bedding to fault angle of near 90° in the footwall and approximately 10° in the hanging wall.

Harris Creek thrust sheet

The Harris Creek thrust sheet maintains a width of about 1.5 km across the entire map area except in the east where the Harris Creek thrust begins to merge with the



Figure 15. Interpreted computer produced plot of the structure at Harris Mountain.

Prospect Creek and Drummond Creek thrusts. Nikanassin, Cadomin, Luscar, Mountain Park and Blackstone strata are contained within the thrust sheet, the older formations being confined to the west and the younger to the east.

Harris Creek thrust

Between the McLeod River and Harris Creek the Harris Creek thrust duplicates the Cadomin Formation. To the east of the Cadomin duplication the fault slowly cuts up section, duplicating the Kennedy seam near MacKenzie Creek. At the eastern boundary of the map area the fault is near the top of the Luscar Formation. Small bedding to fault angles are assumed as the fault trace is sub-parallel to the surface traces of the Cadomin and Kennedy seam. A displacement of the Cadomin Formation in the order of 0.5 km is apparent from profile views.

The thrust sheet

The unit contains several structures which affect the overlying unit such as the Harris Mountain anticline and syncline but also contain several structures which are unique to the unit.

The Harris Mountain anticline affects strata from Nikanassin to Luscar. It has a mean fold axis orientation of 210/3 with a 5° plunge west of Cheviot Creek and a 2° plunge east of Cheviot Creek. The axial plane is believed to be nearly vertical.

A rotational fault occurs in the northeast limb of the Harris Mountain anticline. The fault which appears to dip to the southwest separates the hinge zone of the anticline from the highly disturbed strata in the core of the Harris Mountain syncline between Prospect Creek and the McLeod River (Fig. 13). In the northwest the fault thrusts Nikanassin and Cadomin strata over the Luscar Formation whereas in the east it superimposes Luscar strata on the Nikanassin and Cadomin Formation. Varying fold axis orientations in the folds to either side of the fault substantiate the rotational concept.

The Harris Mountain syncline is the largest structure in this unit affecting strata from the Nikanssin to Mountain Park Formations. In the west, along Prospect Creek, the fold is developed in Nikanassin strata and is upright-plunging with a fold axis orientation of 130/10 and a vertical axial plane. As the fold is traced eastwards younger strata become involved and the fold becomes more complex; at the level of the Cadomin Formation it has split into two synclines and an anticline with orientation for the fold axis and axial

planes of 125/5 and 210/50, respectively. The overturned anticline and syncline either die out or merge with the main syncline as they are traced up section to the east. One broad syncline is present at the height of the Kennedy seam where orientations for the fold axis and axial plane of 125/15 and about 210/80, respectively were obtained. The fold also affects the Prospect Creek thrust along with the Luscar and Mountain Park strata in its hanging wall.

The Harris Mountain thrust fault just north of and parallel to the westerly flowing section of the McLeod River duplicates the Cadomin and separates the highly disturbed core area from the north limb of the Harris Mountain syncline. To the east the fault cuts up section at a low angle being folded by the Harris Creek anticline and syncline before duplicating the Kennedy seam. Further east it is responsible for the major duplication of the Mountain Park Formation before entering the Blackstone Formation 2 km east of MacKenzie Creek. The displacement along this fault increases from west to east due to the absorbtion of the displacement associated with the distorted strata in the Harris Mountain syncline. To the west the fault is believed to parallel bedding near the base of the Nikanassin Formation.

To the north of the Harris Mountain syncline the Harris Creek anticline-syncline pair occur, deforming strata from

Nikanassin to Mountain Park. The folds are associated with the Harris Creek thrust, originating where the Cadomin is truncated in the footwall of the fault. Deformed Cadomin strata are well exposed along the north-south tributary to the McLeod River where a fold axis and axial plane orientation of 130/20 and 25/80 were obtained. The syncline and anticline are well defined at the level of the Kennedy seam by borehole intersections.

MacKenzie Creek thrust sheet

The MacKenzie Creek structural unit contains those strata in the footwall of the Harris Creek thrust and in the hanging wall of the MacKenzie Creek thrust. Strata from the pre-Jurassic map unit up to the Mountain Park Formation in the map area have been affected by structures in this unit. The unit is open at both ends where mapping is less detailed or outcrop lacking.

MacKenzie Creek thrust

The MacKenzie Creek thrust is readily discernible as it duplicates the Cadomin Conglomerate along MacKenzie Creek. The fault while not mapped in detail west of MacKenzie Creek is believed to be present, though undetected, in the

Nikanassin Formation west of the small anticline-syncline pair at 10 000 east and 14 000 north. The fault which has an orientation of 230/40 near MacKenzie Creek, has a displacement of 0.5 km determined from profile measurements assuming movement to have been perpendicular to the fold axis. A marked steepening of strata from the hanging wall to the footwall of approximately 10° is seen across the fault. The eastern extension of the fault beyond 22 000 east is poorly defined due to a lack of exposure.

The thrust sheet

The dominant structures of this unit are an anticline-syncline pair which originates in the pre-Jurassic map unit and affects strata as young as the Blackstone Formation. Two faults cause minor duplication of the Cadomin and surrounding strata in the southern limb of the anticline. In the northern limb of the syncline a small fault is seen to duplicate the Kennedy seam in a borehole while several gentle folds were noted in outcrop. Some highly deformed strata associated with the MacKenzie Creek fault are seen along MacKenzie Creek.

Two small thrusts evident from the duplication of the Cadomin are located to the northeast of Harris Mountain on the south limb of the Cadomin Mountain anticline. The

southern has an orientation of 210/40 and a displacement of approximately 100 m. The other fault has an orientation of 200/30 and a displacement of approximately 100 m. Both faults are lost to the east where they likely merge and result in the duplication of the Kennedy seam before merging with the Harris Creek thrust. To the west due to lack of mapping they cannot be traced for more than one or two kilometers.

The Cadomin Mountain anticline and syncline traceable from bedding orientations and aerial photographs can be traced for 9 km alcng a northwest-southeast trend. In the west along the McLeod River these folds are present as a structural terrace in the pre-Jurassic map unit (Plate 1). An axial plane orientation of approximately 40/80 was obtained for this section. The axial planes become southwesterly dipping when traced to the southeast. At the level of the Cadomin Fcrmation an orientation of 220/50 was obtained accompanied by a fold axis orientation of 130/10. Further to the southeast the folds affect the Kennedy seam and Mountain Park and Blackstone Formation. A fault which duplicates the Kennedy seam along MacKenzie Creek although not noted in outcrop is evident in a borehole log which shows a stratigraphic throw of 32 m. A minor anticline-syncline pair were noted along Swaren Creek above the Cadomin to the east of MacKenzie Creek. While insufficient data were available for an accurate fold axis determination

field evidence points to the folds plunging to the southeast at approximately 20°.

Kryczka thrust sheet

The Kryczka structural unit contains strata from the pre-Jurassic map unit to the Mountain Park Formation. The unit is bounded by the MacKenzie Creek thrust to the southwest and the Kryczka thrust to the southeast. Minor folds and some small displacement faults are the only irregularities in the otherwise homoclinal structure.

The Kryczka thrust

The thrust noted by Kryczka(1959) along MacKenzie Creek is seen to duplicate and triplicate the Cadomin Formation to the east of MacKenzie Creek (MacKay, 1929). To the west the fault probably merges with the MacKenzie Creek fault or cuts down into the Fernie Formation. An orientation of approximately 220/40 for this fault is obtained from map interpretation.

The thrust sheet

While strata as low as the pre-Jurassic unit were investigated only the Luscar and Cadomin Formations were studied to any extent. Several folds associated with the

MacKenzie Creek thrust occur along MacKenzie Creek a short distance to the northeast of this fault. A small fault and associated folds were noted in the central portion of the area while moderate scale folds were noted in the far eastern reaches of the unit.

A small symmetrical anticline about 200 m north along MacKenzie Creek from the MacKenzie Creek fault has a fold axis orientation of 307/10 and a vertical axial plane. This unusual orientation is likely due to uncharacteristic deformation associated with the fault. Other strata in the vicinity of this fold are complexly deformed but assume the common southwesterly dip a short distance to the north. In the central portion of the area a small thrust with an orientation of 220/30 and a small fold with a fold axis orientation of 146/11 were noted along the east-west stream traverse. At the eastern end of the unit an anticline and syncline pair is present. The folds are significant, with a wavelength of 635 m and dips in the common limb of up to 70°. Although not recognized in outcrop the folds are certain to affect the Kennedy seam causing it to wrap around these structures. These folds also explain the excessive Luscar section in this region.

Mesoscopic Structures

Mesoscopic structures not described in the above sections were mapped and recorded whenever encountered. Four types of mesoscopic data were collected: (1) bedding measurements across mesoscopic folds, (2) joint orientations from three formations at three localities, (3) data from a detailed study of the East Pit and (4) fault and slickenside striae.

Mesoscopic fold data were computerized and stored in MP.AXIS. Figure 16 illustrates the positions and orientations of these structures. Several of the folds plunge to the west but the majority are oriented approximately parallel to the mean macroscopic fold axis orientation for the area of 135/15. The mean orientation of the mesoscopic folds is 125/13 with a standard scattering angle of 16.6°. Although not quantitatively analysed, in general the axial planes of these folds dip southwest. Many mesoscopic folds appear to be drag folds closely associated with thrust faults. As such their orientation reinforces the belief that faulting and folding in the Mountain Park area occurred under the same stress system.

Joints with surface areas in excess of 10 sq m were obtained from strata at 3 localities and from 3 stratigraphic intervals. A total of 337 measurements were

Figure 16. Positions and orientations of mesoscopic fold axes in the map area.



Plate 13. Well jointed Cardium sandstones in southern part of map area. Hatchet approximately 40 cm.

taken from the Cardium Formation, Luscar Formation and the pre-Jurassic map unit (Plate 13). In order to compare the joints, orientation diagrams of the poles to joint planes were produced with the orientations rotated so that in all cases the associated bedding planes were horizontal. Figure 17 displays the rotated and unrotated orientation diagrams for the three joint measurement localities. In all cases the joints were normal to bedding. In the Cardium and pre-Jurassic units two well defined joint sets emerged whereas in the Luscar of the East Pit 4 sets were found.

The East Pit, 6 000 sq m in area, was studied in detail, and 58 data stations were plane tabled. The data were stored in the MPEP file. Three map units were used in the study (1) hanging wall, (2) footwall and (3) Kennedy seam. Two folds, called the East Pit anticline and syncline



Figure 17. Joint orientation diagrams. Contour intervals are 1-5%, 6-10% and greater than 10%.

(see p. 62), are exposed in the pit. Plates 14 and 15 show

Plate 14. Looking southeast at the Kennedy seam on the crest of the East Pit anticline. Note extreme deformation.

the style of deformation associated with these folds. Plate 14 illustrates the extremely complex structure which commonly occurs in the axial region of folds in coal-bearing areas. Plate 15 illustrates the reactivated joints which are the most striking structures in the East Pit. The joints which show no displacement but are fully developed near the syncline have increased displacement as they near the crest of the anticline. The constant joint to bedding angle and varied displacement along joints suggest that the joints were formed before this small scale folding occurred which later resulted in the displacement of the joints near the anticline. Appendices 3(f) and 3(d) contain a map of the data stations and orientations as well as a profile plot of

Plate 15. Looking along the intersection of joints and Kennedy seam footwall on crest of East Pit anticline in the pit.

the two folds. Old mine workings below the pit gave a more reliable mean fold axis orientation of 135/10 than the directly measured surface exposures due to the disturbed nature of the strata exposed in the pit. The exposure in the East Pit is the most complex seen in the whole area, due to the excellent exposure and should not be considered as a unique structure.

Some fault and associated slickenside striae orientations were recorded but in such quantities as not to warrant any quantitative analysis. The inability to obtain field measurements on fault planes was due to their near bedding plane attitude which caused them to be very hard to detect.

Discussion

Two excellent marker horizons, the Cadomin Formation and Kennedy seam, provide stratigraphic markers with which one may determine the deformational history of the Mountain Park area. The dominant structures are thrust faults. Faulting generally progressed in a northeasterly direction with movement along younger faults causing folds in the overlying faults and strata. Directions of displacement associated with these thrusts are to the northeast. The thrusts apparently enter zones of *decollement* in the Blackstone Formation to the east and in the lower Nikanassin to the west. Large faults such as the Miette and Fiddle River thrusts are likely to be extensions of several of the faults in the study area. Small fault to bedding plane angles characterize the faults which commonly have displacements exceeding 1 km. Folds are closely associated with the thrust faulting and have a mean fold axis orientation of 135/15 which is parallel to the line of intersection between faults and bedding.

CONCLUSIONS

After 3 months in the field and 14 in the laboratory, all the major objectives of the study have been realized. The computer has been used effectively to store, retrieve and process many of the surface and subsurface data accumulated. The thicknesses of the Luscar and Mountain Park Formations have been revised from 490 m to 380 m and from 120 m to 200 m, respectively, and the number of significant coal seams in the Luscar reduced from 11 to 4. These seams are thought to be much more extensive than previously envisaged; one seam has been correlated all the way from Nordegg, Alberta into northeastern British Columbia. Instead of the six steeply dipping thrust and normal faults with displacements of about 0.5 km that were mapped by MacKay (1929), the Mountain Park area is now thought to be crossed by five thrust faults that cut up section to the northeast at about 5° to bedding and that have a cumulative displacement of about 10 km. These faults, which appear to be splays from the McConnell and Miette thrusts, flatten and merge in the Blackstone Formation. The structure of the area is illustrated by a geological map at a scale of 1:25 000 and by cross sections constructed using a computerized down-plunge projection technique.

REFERENCES

Alberta, Government of. 1976. A Coal Development Policy for Alberta. Dept. of Energy and Natural Resources Government of Alberta, Edmonton, Alberta.

Allan, J.A. and Rutherford, R.L. 1924. Some Coal-Seam Correlaticn Problems from McLeod to Athabasca River. Res. Coun. Alta. Rpt. 11.

Best, E.W. 1966. A Note on the Triassic Whitehorse Formation of the Type Section. in Edmonton Geol. Soc. 8th Annual Field Trip, Guidebook. Cadomin, pp. 61-66.

Busk, H.G. 1929. Earth Flexures. London, Cambridge University Press.

Charlesworth, H.A.K., Langenberg, C.W. and Ramsden, J. 1976. Determining Axes, Axial Planes and Sections of Macroscopic Folds Using Computer-Based Methods. Can. Jour. Earth Sci., 13, pp. 54-65.

Douglas, R.J.W. 1956. Preliminary Map And Report, Nordegg, Alberta. Geol. Surv. Can. Pap. 55-34.

Dowling, D.B. 1910. Coal Fields South of the Grand Trunk Pacific Railway, in the Foothills of the Rocky Mountains, Alberta. Geol. Surv. Can., Summ. Rpt. 1909, pp. 139-150+map.

--------- 1915. Coal Fields and Coal Resources of Canada. Geol. Surv. Can. Mem. 59.

Frebold, H. 1957. The Jurassic Fernie Group in the Canadian Rocky Mountains and Foothills. Geol. Surv. Can. Mem. 289.

Gibson, D.W. 1978. The Kootenay-Nikanassin Lithostratagraphic Transition, Rocky Mountain Foothills of West-Central Alberta. Geol. Soc. Can. Pap. 78-1A pp. 94-106.

Hacquebard, P.A. and Donaldson, J.R. 1974. Rank Studies of Coal in the Rocky Mountains and Inner Foothills Belt Canada. Geol. Surv. Can. Spec. Pap. 153 pp. 75-94.

Hake, B.F., Willis,R. and Addison,C.C. 1942. Folded Thrust Faults In The Foothills Of Alberta. Geol. Soc. Amer. Bull. 53, pp.291-334.

Holter, M.E. and Mellon, G.B. 1972. Geology of the Luscar (Blairmore) Coal Beds, Central Alberta Foothills. 1st Geol. Conf. of W. Can. Coal, Edmonton, Alta. Res. Coun. Alta. Inform. Ser. No. 60.

Kryczka, A.A.W. 1959. The Nikanassin of The Type Area, near Cadomin, Alberta. unpub. M.Sc. thesis, Dept. of Geol., University of Alberta.

Langenberg, C.W., Rondeel, H.E. and Charlesworth, H.A.K. 1977. A Structural Study in the Ardennes with Section Constructed Using Computer-Based Methods. Geol. Mijnbouw 56, pp. 145-154.

MacKay, B.R. 1929. Mountain Park, Alberta. Geol. Surv. Can. Map 208A.

________ 1930. Stratigraphy and Structure of Bituminous Coalfields in the Vicinity of Jasper Park, Alberta. Can. Inst. Mining Metall. Trans. Bull. 222 pp. 473-509.

________ 1947. Coal Resources Of Canada, reprint of Chapter 1 and Appendix A of Report of the Royal Commision on Coal, 1946.

Mardia, K.V. 1972. Statistics of Directional Data. Academic Press, London.

McLean, J.R. 1977. The Cadomin Formation: Stratigraphy, Sedimentology and Tectonic Implications. Can. Soc. of Petrol. Geol. Spec. Publ. 25, pp. 792-827.

Mellon, G.B. 1964. Descriminatory Analysis Of Calcite And Silicate Cemented Phases Of The Mountain Park Sandstone. Jour. of Geol. 72, pp.786-809.

________ 1966. Lower Cretaceous Section, Cadomin Area, Alberta. Edmonton Geol. Soc. 8th Annual Field Trip Guidebook, Cadomin. pp. 67-79.

Mortimer, P. 1978. The Alpine Vascular Flora and Vegitation of Prospet Mountain, Front Ranges, Rocky Mountains, Alberta. unpub. M.Sc. thesis, Dept. of Botany, University of Alberta.

Perry, M. and Butler,B. 1974. Graphitizer, The Digitizer. University of Alberta.

Ross, T. 1974. Oh The Coal Branch. D.W. Frieson and Sons Ltd., Calgary, Alberta.

Stewart, J.B. 1917. Coal Mines of West Central Alberta. Geol. Surv. Can. Summ. Rpt. 1916, pp. 94-106.

Stott, D.F. 1963. The Cretaceous Alberta Group and Equivalent Rocks, Rocky Mountain Foothills,Alberta. Geol. Surv. Can. Mem. 317.

________ 1966. Cretaceous Alberta Group in the Region of McLeod River, Alberta. Edmonton Geol. Soc. 8th Annual Field Trip Guidebook, Cadomin. pp. 379-381.

________ 1968. Lower Cretaceous Bullhead and Fort St. John Groups, between Smoky And Peace Rivers, Rocky Mountain Foothills, Alberta and British Columbia. Geol. Sur. Can. Bull. 152.

________ 1974. Lower Cretaceous Coal Measures of the Foothills of West-Central Alberta and Northeastern British Columbia. C.I.M.M. Bull. 67, No. 749, pp. 87-100.

Warren, P.S. and Stelck, C.R. 1958. The Nikanassin-Luscar Hiatus in the Canadian Rockies. Trans. Royal Soc. Can. 52, No. 13, pp. 55-62.

Wrightson, C.B. 1978. Structural Geology and Stratigraphy of the Campbell Anticlinorium, Grande Cache, Alberta. unpub. M.Sc. thesis, Dept. of Geology, University of Alberta.

APPENDIX 1

Formats and Partial Listings of the O/C,MP.AXIS,MPDH,MPMW and MPEP Files Used to Store Data.

(a) The O/C File

Format

Column	Data
1-3	Identification number.
6-11	Northing or y coordinate.
13-18	Easting or x coordinate.
20-23	Elevation or z coordinate.
25	Alphabetic code designating stratigraphic position: K= Cardium Formation B= Blackstone Formation E= Mountain Park-Blackstone contact M= Mountain Park Formation L= Luscar Formation C= Cadomin Formation N= Nikanassin Formation F= Fernie Group P= Pre-Jurassic (undivided)
27	Binary code indicating whether or not significant uncodeable information occurs on field data sheet: 1= Yes 0= No
29	Numeric code indicating confidence in outcrop coordinates. Scale from 1 tc 9 being extremely accurately located to poorly located, respectively.
31	Number of bedding plane orientations recorded.
33-53	Dip directicns of bedding.
55-75	Dips of bedding.
76-83	Mean dip direction and dip obtained after processing above readings (see p. 21).
84-93	Concentration parameter, specifying scatter of original measurements of bedding about mean, obtained after processing above readings (see p. 22).

Partial Listing

[illegible]	[illegible]	[illegible]	7150?	[illegible]			[illegible]	[illegible]	125130130133123?	62.	129.	141.55
[illegible]	[illegible]	[illegible]	7100	[illegible]			[illegible]	[illegible]	120120121122130?	67.	124.	141.80
[illegible]	[illegible]	[illegible]	[illegible]				[illegible]	[illegible]	021022022022023?	214.	22.	421.00
[illegible]	[illegible]	[illegible]	5000	[illegible]			[illegible]	202192233207190?	022022022022023?	205.	23.	108.34
[illegible]	[illegible]	-16732?	[illegible]	[illegible]	[illegible]		[illegible]	236247222239257?	025025027024010?	245.	24.	153.81
[illegible]	[illegible]	[illegible]	5775?	[illegible]			5	207211243217236?	030034022025027?	221.	27.	65.64
[illegible]	[illegible]	[illegible]	5750	[illegible]			[illegible]	[illegible]	030032018018022?	182.	25.	67.10
[illegible]		-17900?	5725	[illegible]			[illegible]	[illegible]	041041037036042?	214.	40.	192.4?
[illegible]		-17579	5725	[illegible]			5	207200137214202?	031022030030027?	202.	28.	134.50
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	0					0.0
[illegible]	[illegible]	[illegible]	5700	L			[illegible]	[illegible]	044051043049049?	211.	40.	500.99
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]			5	[illegible]	063058000000058?	206.	62.	50.31
[illegible]	11040?	[illegible]	[illegible]	[illegible]			5	[illegible]	055056052046057?	212.	54.	105.92
[illegible]	[illegible]	-15779	[illegible]	[illegible]			6	[illegible]	040038037031040036?	210.	37.	222.40
[illegible]	[illegible]	-15407?	5010?	[illegible]	[illegible]	1	0					0.0
[illegible]	[illegible]	[illegible]	5555?	[illegible]	1	[illegible]	5	234218214220221?	047050049047047	218.	48.	813.40
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]			5	[illegible]	021022010018040?	215.	23.	44.34
[illegible]	[illegible]	[illegible]	5575	[illegible]	[illegible]		5	[illegible]	070077080080074?	37.	76.	[illegible]
[illegible]	[illegible]	-14501?	5555	[illegible]	[illegible]	0	5	[illegible]	022013010018021?	140.	17.	142.57
[illegible]	[illegible]	[illegible]	[illegible]		1	[illegible]	5	167190184195165?	024031024031027?	169.	27.	[illegible]
[illegible]	[illegible]	16705?	5650	L		0	5	[illegible]	029027025027024?	209.	20.	552.27
[illegible]	[illegible]	[illegible]	5650	[illegible]	1	[illegible]	[illegible]	[illegible]	050057057050048?	218.	53.	121.12
[illegible]	[illegible]	[illegible]	5000?	L		0	[illegible]	[illegible]	041039030031041?	212.	37.	223.07?
[illegible]	[illegible]	16433?	5000	L	1	[illegible]	5	[illegible]	033030033032030?	210.	33.	670.02?
[illegible]	[illegible]	[illegible]	6025	[illegible]		6	5	[illegible]	030039037041030?	237.	38.	[illegible]
[illegible]	[illegible]	[illegible]	5545	L			5	142144153153158?	028027023030027?	142.	27.	203.32?
[illegible]	[illegible]	[illegible]	5550	L			5	[illegible]	024029024025025?	163.	25.	561.04?
[illegible]	[illegible]	[illegible]	5575	L	[illegible]	[illegible]	[illegible]	[illegible]	023030023031033?	81.	28.	173.75
[illegible]	[illegible]	[illegible]	[illegible]	L		[illegible]	[illegible]	[illegible]	024027023021025?	130.	24.	510.0?
[illegible]	[illegible]	[illegible]	5000	L		[illegible]	[illegible]	[illegible]	015013018016013?	177.	14.	660.75?
[illegible]	[illegible]	[illegible]	5020	[illegible]		[illegible]	[illegible]	[illegible]	[illegible]	179.	21.	151.9?
[illegible]	[illegible]	[illegible]	5025	[illegible]		[illegible]	[illegible]	[illegible]	[illegible]	178.	23.	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	194.	26.	231.9?
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]		[illegible]	[illegible]	[illegible]	[illegible]	191.	30.	45.80?
[illegible]	[illegible]	[illegible]	[illegible]					[illegible]	[illegible]	192.	25.	239.7?
[illegible]	[illegible]	[illegible]	5700?					[illegible]	[illegible]	197.	26.	[illegible]

(b) The MPDH File

Format

Column	Data
1-5	Identification number. To facilitate handling, original designations of some holes in records of Consolidation Coal Company of Canada have been altered. Whereas M.P.West holes retain their original numerical designations, 500 has been added to those of M.P.East holes. Decimals have been used to identify separate holes drilled at same location.
7	Alphabetic code designating horizons picked: S= Topographic surface A= Base of Kennedy(a) seam B= Base of Kennedy(b) seam C= Base of Thornton seam D= Base of ST1 (probably Michelin or Thornton) seam F= Base of Michelin seam G= Base of Cheviot seam
9-14	Northing or y coordinate.
16-21	Easting or x coordinate.
23-26	Elevation or z coordinate.
28	Alphabetic code designating sources of information used to identify horizon picked: A= Gamma, resistivity and driller's logs B= Gamma and resistivity logs C= Gamma and driller's logs D= Resistivity and driller's logs E= Driller's logs F= None of the above
30	Binary code indicating identification reliability: 0= Excellent 1= Good

Partial Listing

146.0	A	4659	-16259	5972	A	0
146.0	S	4659	-16259	6125	A	0
146.0	B	4659	-16259	5926	A	0
145.0	B	4906	-16235	5992	A	0
145.0	A	4906	-16235	6027	A	0
145.0	S	4906	-16235	6113	A	0
160.0	S	4929	-16041	6088	A	0
160.0	A	4929	-16041	5532	A	1
50.0	S	4656	-16037	6114	A	0
50.0	A	4656	-16037	5921	A	0
144.0	S	4774	-15934	6094	A	0
144.0	B	4774	-15934	5977	A	0
29.0	S	4631	-15800	6112	A	0
29.0	B	4631	-15800	5945	A	0
29.0	A	4631	-15800	5963	A	0
15.0	A	6086	-15511	5804	A	0
15.0	E	6086	-15511	5788	A	0
15.0	S	6086	-15511	5984	A	0
10.0	A	5786	-15059	5759	A	0
10.0	S	5786	-15059	6031	A	0
10.0	B	5786	-15059	5749	A	0
16.0	S	4176	-15040	6078	A	0
16.0	A	4176	-15040	5909	A	0
16.0	B	4176	-15040	5877	A	0
12.0	S	6033	-15036	6039	A	0
12.0	B	6033	-15036	5886	A	0
12.0	A	6033	-15036	5898	A	0
18.3	A	6175	-14996	5972	A	0
18.3	B	6175	-14996	5961	A	0
18.3	S	6175	-14996	6040	A	0
14.0	S	4673	-14984	6061	A	0
14.0	B	4673	-14984	5970	A	0
14.0	A	4673	-14984	5984	A	0
18.1	B	5864	-14817	5937	A	0
18.1	A	5864	-14817	5927	A	0
18.1	S	5864	-14817	6037	A	0

(c) The MPMW File

Format

Column	Data
1-4	Identifications number.
6-11	Easting or x coordinate.
13-18	Northing or y coordinate.
20-23	Elevation or z coordinate.
25	Binary code indicating whether Kennedy seam is in hanging wall or footwall of Drummond Creek thrust. Author's Kennedy seam is referred to on mine plans as "Kennedy seam" in hanging wall and "#3 seam" in footwall: 0= Footwall 1= Hanging wall
27	Binary code indicating whether data station is underground or at surface: 0= Underground 1= Surface
29	Binary code indicating whether or not orientation data are available: 0= No 1= Yes
31-36	Dip direction and dip of bedding.

Partial Listing

2046	1567	-8650	5709	1	0	1	093020
2047	1152	-9210	5714	1	0	1	113035
2048	1513	-9230	5716	1	0	1	222050
2049	1405	-9375	5718	1	0	1	119047
2050	1635	-9698	5720	1	0	1	215050
2051	1891	-10135	5724	1	0	1	194037
2052	1945	-10280	5726	1	0	1	206030
2053	2073	-10530	5729	1	0	1	206035
2054	2317	-10928	5734	1	0	1	205028
2055	2425	-11097	5737	1	0	1	213025
2056	2605	-11452	5741	1	0	1	205022
2057	2676	-11630	5743	1	0	1	200020
2058	2863	-12133	5748	1	0	1	195020
2059	2832	-12437	5757	1	0	1	183023
2060	2625	-12545	5759	1	0	0	
2061	-1560	35	5555	0	0	0	
2062	-1435	12	5545	0	0	0	
2063	-866	37	5669	0	0	0	
2064	-312	-11	5918	0	1	0	
2065	-312	14	5922	0	1	0	
2066	-1559	244	5552	0	0	0	
2067	-1340	261	5552	0	0	0	
2068	-1271	260	5554	0	0	0	
2069	-1264	375	5554	0	0	0	
2070	-1304	502	5556	0	0	0	
2071	-1338	615	5557	0	0	0	
2072	-1294	770	5557	0	0	0	
2073	-1264	867	5559	0	0	0	
2074	-1286	983	5559	0	0	0	
2075	-1276	1070	5559	0	0	0	
2076	-1242	1129	5560	0	0	0	
2077	-1198	1123	5560	0	0	0	
2078	-1091	1058	5563	0	0	0	
2079	-1026	1044	5564	0	0	0	
2080	-1058	1117	5566	0	0	0	
2081	-1074	1175	5567	0	0	0	

(d) The MPEP File

Format

Column	Data
	First line
1-3	Identification number: 1-51 for data stations and 501-507 for survey turning hubs.
5-10	Northing or y coordinate.
12-17	Easting or x coordinate.
19-22	Elevation or z coordinate.
24	Code designating map unit: 1= Footwall 2= Footwall - coal interface 3= Coal 4= Hanging wall - coal interface 5= Hanging wall
26	Number of bedding plane orientations recorded.
28-42	Dip directions of bedding.
44-58	Dips of bedding.
60	Number of joint orientations.
62-79	Dip directions of joints.
	Second Line
1-18	Dips of joints.

Partial Listing

```
 1   [illegible]    47     4 2 5 0[illegible]04[illegible]0[illegible]051052 07[illegible]074[illegible]07[illegible]74 2 3[illegible]155
[illegible]
 2   -[illegible]   [illegible]  10 2 5 04[illegible]04[illegible]04[illegible]040 07707407[illegible]75077 4 3[illegible]1172144309
[illegible]
 3   -[illegible]    [illegible]  4 2 5 [illegible]05[illegible]04[illegible]03 07[illegible]7[illegible]0[illegible]7[illegible]09 [illegible]

 [illegible]   -[illegible]   -[illegible]   4 2 5 [illegible]4404[illegible]04[illegible]044 [illegible]5[illegible]07[illegible]074 1 3[illegible]
[illegible]
 5   -4    -42   [illegible] 2 5 [illegible]4[illegible]044[illegible]4[illegible]4[illegible]044 0520930070[illegible]0093 4 12912413012[illegible]
[illegible]
 6   1[illegible]   -[illegible]   [illegible] 2 5 04[illegible]4[illegible]3[illegible]0[illegible] [illegible]0707[illegible]70[illegible]30711 4 [illegible]321[illegible]135290
[illegible]
 7   [illegible]   -[illegible]   [illegible] 2 5 0[illegible]047[illegible]4004[illegible]035 0[illegible]077[illegible]7[illegible]0[illegible]07[illegible] 1 131
[illegible]
 [illegible]   72    -[illegible]   [illegible] 2 5 [illegible]7[illegible]77[illegible]7[illegible]1[illegible]187 04204[illegible]059357065 1 312
[illegible]77
 9   [illegible]1   -[illegible]   15 2 5 [illegible]9[illegible]0[illegible]5[illegible]0197 054049049040049 6 304338[illegible]4[illegible]110[illegible]9729
074[illegible]9[illegible]4[illegible]07[illegible]0[illegible]7
 10  5[illegible]   1[illegible]   14 1 5 1[illegible]7[illegible]1[illegible]21[illegible]1177 0330[illegible]040041030 0

 11  [illegible]1    7    27 1 5 1[illegible]1207193[illegible]3171 036076050040037 0

 12  9[illegible]    2    30 2 5 1[illegible]742100170101 041030032035030 0

 13  7[illegible]   -[illegible]   29 1 5 175177174[illegible]7 041049044051039 2 311230
04[illegible]9
 14  [illegible]   [illegible]   40 4 5 1[illegible]7[illegible]0[illegible]0[illegible]3[illegible]0 054049043043047 3 023030201
[illegible]
 15  4[illegible]   [illegible]9   32 3 5 1[illegible]7204[illegible]2133190 025034035045031 0

 16  17    77   [illegible] 5 5 121128129130[illegible] 041041048044039 0

 17  -[illegible]   10[illegible]   15 5 5 0[illegible]608[illegible]5085092 036036043044041 5 326320213267213
049049054[illegible]50
 18  4[illegible]   -119   56 2 5 05[illegible]50048047044 049064060068074 0
```

(e) The MP.AXIS File

Format

Column	Data
	First line
1-3	Identification number.
5-10	Easting or x coordinate.
11-16	Northing or y coordinate.
17-22	Elevation or z coordinate.
24	Binary code indicating whether or not orientation data from this outcrop are in O/C file: 0= No 1= Yes
26	Numeric code indicating type of folding present: 1= Anticline 2= Syncline 3= Series of folds
28	Alphabetic code designating stratigraphic position (see description of column 25 of O/C file).
30-31	Number of bedding plane orientations.
33-80	Bedding plane orientations in an integrated format with dip directions interspersed with dips.
	Second line
1-42	As in columns 33-80 of first line.
45-50	Trend and plunge of best-fit fold axis obtained after processing above readings (see p. 21).

Partial Listing

```
516  21767  5446  5505 0 1 L  5 06104707603 0850161550131960 12
                                            140011
494  15457  6775  5456 0 1 L  5 2460272536 1032401101061602654
                                            307018
730  15216  0378  5475 1 1 F  5 047147 00111 057089127826195038
                                            157023
492  11013  0507  5-75 0 1 F  6 13 1252 18 0519101621 5 . 6030 9162 03
                                            105002
144  -5320  5068  5710 1 2 L  5 17701515765715305111204309054
                                            161024
706  -2340  5072  5710 1 1 L  6 0530360052050037041192013144011202032
                                            122000
207  -2470  5054  5705 1 2 L  6 2000421956510990180340590270900026106
                                            119012
728  -2293  4000  5715 1 1 L 10 197007151008202084154095151104197040187027043005
0290353023049                               107004
427  -2104  5524  5090 0 1 L 12 0300640250200380700410050470570416490440270060009
2210512230211000300118023                   126003
505  -1304  7172  5770 1 1 X  6 1550140730071570131350131450160140009
                                            087007
725   -406 -2605  5900 0 2 F  4 067103075000090059195042
                                            162054
721   -721 -3406  5950 0 3 R 10 2190132130050340430400700330270280300310052500008
2510272026023                               367002
362   2138 -1114  0383 0 1 F  5 1040201250131390131250141400019
                                            144015
718   2765   100  5050 0 1 L 11 149005078007075024059033055030047024031121049035
0420430430358052057                         130006
357   3049 13301  7225 0 3 N 14 130035176030175030170030121023063030137025054031
045032046034040104022058013000002103        123020
377   4027  -924  6940 0 1 E  5 102011130015192010105023203041
                                            126011
352   4104 10324  7150 0 2 R 11 130041104030175030130032101022103076059024005024
0490540290007 2037                          120019
365   4004  1130  3070 0 2 F  5 0030220990 7056019003022047054077060083114031090
                                            132010
```

APPENDIX 2

Retrieval Programs, Run Commands and the AR-File

Source Listing of the Program STATION

```
C*******  DESIGNED TO EXTRACT SPECIFIED OUTCROPS AND PUT THE PERTINANT
C         INFORMATION IN A FORMAT AMENABLE TO CYLTEST, ETC.
      INTEGER STA,ST,X,Y,Z,F,DD,D
      INTEGER SLASH/'/'/
      INTEGER CODE/'*'/
101   READ(1,10,END=51)STA
100   READ(5,11,END=52)ST,Y,X,Z,F,DD,D
      IF(STA .NE. ST)GO TO 50
      X=X+32000
      Y=Y+16000
      IF(D .LT. 90)  GO TO 1
      DD=DD+180
      IF(DD .GT. 360)  DD=DD-360
      D=90-(D-90)
      WRITE(6,14)F,X,Y,Z,DD,D,CODE,ST
      GO TO 53
1     WRITE(6,12)F,X,Y,Z,DD,D,ST
      GO TO 53
 52   CONTINUE
      REWIND 5
53    CONTINUE
      GO TO 101
 50   CONTINUE
      GO TO 100
 51   CONTINUE
      WRITE(6,13)SLASH
 10   FORMAT(I3)
 11   FORMAT(I3,2X,I6,1X,I6,1X,I4,1X,A1,50X,I3,1X,I3)
 12   FORMAT(A1,I5,I5,I5,1X,I3,I3,5X,I3)
 13   FORMAT(A1)
14    FORMAT(A1,I5,I5,I5,1X,I3,I3,1X,A1,3X,I3)
      STOP
      END
```

Source Listing of the Program COALADD

```
C*****COALADD READS THE MPDH FILE AND THE USER
C     INPUT LIMITS OF INTEREST TO PRODUCE A FILE OF
C     BORE-HOLE INTERSECTIONS WHICH CAN BE ADDED TO AN
C     AR-FILE.
C
C
      INTEGER CODE,X,Y,Z,COAL/'A'/,NEWCO/'1'/,XMIN,XMAX,
     *YMIN,YMAX
      READ(6,10)XMAX,XMIN,YMAX,YMIN
      DO 1 I=1,1000
      READ(5,11,END=9)CODE,Y,X,Z
      IF(CODE .NE. COAL)  GO TO 1
      IF(X .LT. XMIN)  GO TO 1
      IF(X .GT. XMAX)  GO TO 1
      IF(Y .LT. YMIN)  GO TO 1
      IF(Y .GT. YMAX)  GO TO 1
      X=X+32000
      Y=Y+16000
      WRITE(7,12)NEWCO,X,Y,Z
1     CONTINUE
10    FORMAT(4I10)
11    FORMAT(6X,A1,2(1X,I6)1X,I4)
12    FORMAT(A1,3I5)
9     STOP
      END
```

Source Listing of the Program COALADD1

```
C***** COALADD1 READS THE MPMW FILE AND THE USER
C       INPUT LIMITS OF INTEREST TO PRODUCE A FILE
C       OF COAL OCCURENCES LOCATED IN OLD MINE-WORKINGS
C       WHICH CAN THEN BE ADDED TO AN AR-FILE.
C
C
      INTEGER CODE,X,Y,Z,DD,DI,XMAX,XMIN,YMAX,YMIN
      READ(6,10)XMAX,XMIN,YMAX,YMIN
      DO 1 I=1,1000
      READ(5,11,END=9)Y,X,Z,CODE,DD,DI
      IF(X .GT. XMAX)  GO TO 1
      IF(X .LT. XMIN)  GO TO 1
      IF(Y .GT. YMAX)  GO TO 1
      IF(Y .LT. YMIN)  GO TO 1
      X=X+32000
      Y=Y+16000
      WRITE(7,12)NEWCO,X,Y,Z
1     CONTINUE
10    FORMAT(4I10)
11    FORMAT(5X,I6,1X,I6,1X,I4,1X,A1,5X,2I3)
12    FORMAT(A1,3I5,1X,2I3)
9     STOP
      END
```

Run Commands for STATION, COALADD and COALADD1

Run sequence

```
#$RUN STATION 1=*MSOURCE* 5=O/C 6=-OUTPUT1
  (user types in required station numbers in I3 format)
#$RUN COALADD 1=*MSOURCE* 5=MPDH 6=-OUTPUT2
  (user types in the X and Y limits in 4I6 format)
#$RUN COALADD1 1=*MSOURCE* 5=MPMW 6=-OUTPUT3
  (user types in the X and Y limits in 4I6 format)
#$COPY -OUTPUT1+-OUTPUT2+-OUTPUT3 TO -OUTPUT4
  (stores outcrop, mine and bore-hole data in -output4)
#$EDIT -OUTPUT4
:INSERT .5
?2 DOMAIN 15
?
:RENUMBER
:STOP
#$GET -OUTPUT4
#READY
#$NUMBER LAST+1
#     21_/
#     22_$UNNUMBER
```

Format of the AR-File Produced by STATION, COALADD and COALADD1

Column	Data
	First line
1	Numeric code specifying type of orientation data in file: 1= Trend and plunge 2= Dip direction and dip
3-40	Title
	Second to second last lines
1	Code designating stratigraphic position. Numeric codes 0 and 1 were used for Kennedy seam in mine workings and borehole intersections, respectively, whereas alphabetic codes described in column 25 of O/C file were used to designate formations at outcrops.
2-6	Easting or x coordinate.
7-11	Northing or y coordinate.
12-16	Elevation or z coordinate.
18-20	Mean dip direction.
21-23	Mean dip.
25	A blank or an asterisk indicating that strata are right way up or overturned, respectively. Thus an orientation of 219/88 with an asterisk is in reality 39/92.
26-29	Station number. These columns were left blank when data came from MPDH,MPMW and MPEP files.
31	Number of orientation readings.
32-41	Concentration parameter.
46-52	Single measurement of bedding randomly selected from O/C file, required in a cylindricity test (see p. 25).
	Last line
1	Slash indicating end of file.

Example of an AR-File

2 DOMAIN 15

M3355913724	6000	48	59		29	5	59.52	46	59
M3310013749	5970	51	56		30	5	138.44	55	57
M3290513654	5955	51	56		33	5	85.86	64	60
M3277313890	5945	219	88	*	34	5	120.46	35	96
M3267313903	5935	46	76		35	5	111.26	55	77
M3217113972	5920	213	78	*	36	5	16.34	39	77
M3184014338	5885	64	26		37	5	429.74	70	25
M3121912520	5950	37	31		38	5	139.96	39	33
B3140911999	6000	38	44		39	5	145.35	41	52
M3122012764	5915	45	56		40	5	633.45	45	56
M3132912971	5910	52	53		41	5	155.13	45	51
M3156913295	5925	93	13		42	5	133.60	79	21
M3153413391	5900	77	31		43	5	169.75	69	33
03208514640	5555								
03201214565	5545								
03203715134	5669								
03198915688	5918								
03208415686	5922								
13738420868	5627								
13747220929	5706								
13765121019	5832								
13827520783	5845								
13827520706	5733								
13829422212	5957								
13830722092	5907								
13999721462	5660								
14001121616	5866								

APPENDIX 3

Programs and Procedures used in the Processing of Structural Data

(a) Program EIGENMEAN

```
C***** THIS ROUTINE IS TO BE USED TO FIND THE EIGEN VECTORS
C        ASSOCIATED WITH THE MAXIMUM EIGEN VALUES.  THE SUBROUTINE
C        IS TO BE INCORPORATED INTO A PROGRAM TO DETERMINE
C         THE AVERAGES OF THE ORIENTATIONS FROM THE O/C
C         FILE.
C
C
       SUBROUTINE [illegible] (A,[illegible],[illegible],T,P,N)
        REAL [illegible](6),[illegible](9),DDD(3000)
      REAL RR(3,3)
       [illegible] DD(10),DIP(10),[illegible]/00/
      [illegible] ([illegible],RR)
      REAL X(10),Y(10),Z(10)
       INTEGER N
      DO 2 I=1,N
      X(I)=DD(I)
      Y(I)=DIP(I)
2     CONTINUE
      I=0
      CALL DC(X,Y,Z,N)
       DO 20 I=1,6
20     M(I)=0
      DO 30 I=1,N
      A=X(I)
      B=Y(I)
      G=Z(I)
       M(1)=M(1)+A*A
       M(2)=M(2)+A*B
       M(3)=M(3)+B*B
       M(4)=M(4)+A*G
       M(5)=M(5)+B*G
       M(6)=M(6)+G*G
30     CONTINUE
       CALL EIGEN(M,R,3,0)
       CALL TPDT(R(1),R(2),R(3),X(1),X(2))
       R(3)=R(1)
       T=X(1)
       P=X(2)
       E=R(3)
       RETURN
       END
      SUBROUTINE DC(U1,U2,U3,N)
      REAL U1(N),U2(N),U3(N)
      CALL DGRD(U1,N)
      CALL DGRD(U2,N)
      CALL DDTP(U1,U2,N)
      CALL TPDC(U1,U2,U3,N)
      RETURN
      END
      SUBROUTINE DGRD(A,N)
C   CONVERT TO RADIANS
      REAL A(N)
      REAL PI/3.14159265/,TWOPI/6.2831853/,HALFPI/1.57079633/
      DO 100 I=1,N
100   A(I)=A(I)*1.745329252E-2
      RETURN
      END
      SUBROUTINE DDTP(A,B,N)
C   CONVERT DD AND DIP (RADIANS) TO TREND AND PLUNGE (RADIANS)
      REAL A(N),B(N)
      REAL  PI/3.14159265/,TWOPI/6.2831853/,HALFPI/1.57079633/
      DO 100 I=1,N
      C=A(I)+PI
      IF(C .GT. TWOPI)C=C-TWOPI
      A(I)=C
100   B(I)=HALFPI-B(I)
      RETURN
      END
      SUBROUTINE TPDC(A,B,G,N)
C   TO CONVERT TREND AND PLUNGE RADIANS TO DIRECTION COSINES
      REAL A(N),B(N),G(N)
      REAL PI/3.14159265/,TWOPI/6.2831853/,HALFPI/1.57079633/
      DO 100 I=1,N
      TR=A(I)
      PL=B(I)
      COSP=COS(PL)
      A(I)=COS(TR)*COSP
      B(I)=SIN(TR)*COSP
100   G(I)=SIN(PL)
      RETURN
      END
```

(b) Program STEREO

PURPOSE: To Extract the orientation data from an AR-File and place them in another file, -data, which is then operated on by FINPUT, PLOT and EIGEN.

```
C***** USED TO CONVERT 'AR-FILE' TYPE DATA INTO A FORMAT
C       AMENABLE TO THE ANALIZING PROGRAMS.
      INTEGER DD,SLASH/'/'/,DI
      INTEGER LINE(40)
      INTEGER FM
      READ(5,12)(LINE(I),I=1,40)
      WRITE(6,12)(LINE(I),I=2,40)
      WRITE(6,13)
      DO 1 K=1,500
      READ(5,10,END=9)FM,DD,DI
      IF(FM .EQ. SLASH)  GO TO 9
      IF(DD .NE. 0)GO TO 2
      IF(DI .EQ. 0)  GO TO 1
2     WRITE(6,11)DD,DI
1     CONTINUE
10    FORMAT(A1,16X,2(I3))
11    FORMAT(2(I3,1X))
12    FORMAT(40A1)
 13   FORMAT('TYPE=2')
14    FORMAT('END')
9     WRITE(6,14)
      STOP
      END
```

(c) Procedure for Testing Cylindricity

Data from the East Pit are used below to illustrate the procedures followed in establishing domains within which folding can be considered cylindrical (see p. 25). The chi-square statistic with which to test the cylindricity of a potential domain,

$$K\lambda_3 > \chi^2_{p-2}(\alpha)$$

requires (1) the value of λ_3 calculated using original orientations of bedding collected in the field and stored in columns 46-52 of the AR-file for the East Pit and (2) the pooled estimate K of the concentration parameters stored in columns 32-41. In the case of the East Pit these values were found to be 0.8563 and 65.72, yielding a value for the statistic of 56.26. The critical value of χ^2 with $\alpha = 0.05$ is 66.34. Thus the null hypothesis of cylindricity associated with the χ^2 test could not be rejected; i.e. this test suggests that folding within the entire East Pit can be considered cylindrical.

The F statistic,

$$(p-4)(\lambda_3 - \lambda_{3a} - \lambda_{3b})/2(\lambda_{3a} + \lambda_{3b}) > F_{2,p-4}(\alpha)$$

requires the running of EIGEN or CYLTEST using the mean orientations from both the whole and both halves of the East Pit. In the East Pit the resultant value was 22.07 while the F-critical value is 3.20 where $\alpha = 0.05$ which leads to the null hypothesis of cylindricity being rejected; i.e. this

test suggests that folding within the East Pit can not be considered cylindrical.

An examination of the fold axis orientations and eigenvalue relationships (see computer printout below) showed that the two halves of the East Pit, EPN and EPS, contain well defined fold axis orientations of 125/30 and 128/14, respectively, with standard scattering angles of about 5.5°. The strong rejection of the F-test along with

EP
50 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
234.3	38.1	27.8125	0.556251
9.3	42.1	21.3525	0.427049
123.5	24.4	0.8347	0.016693

EPN
30 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
9.4	36.7	16.3911	0.546368
242.7	38.7	13.3497	0.444989
125.0	30.2	0.2592	0.008639

EPS
20 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
230.6	42.3	14.6371	0.731854
23.8	44.4	5.1880	0.259398
127.7	13.8	0.1749	0.008745

EPNW
13 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
14.6	26.3	8.7023	0.669407
253.0	46.6	4.2213	0.324718
122.4	31.6	0.0763	0.005873

EPNE
17 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
275.9	57.2	9.4163	0.553901
29.9	14.6	7.4411	0.437715
128.1	28.6	0.1425	0.008383

EPSW
13 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
230.8	43.2	10.4127	0.800978
22.8	43.2	2.4473	0.188253
126.8	14.5	0.1400	0.010767

EPSE
6 POINTS

EIGENVECTOR TREND	EIGENVECTOR PLUNGE	EIGENVALUE	EIGENVALUE/N
236.4	51.2	3.9822	0.663699
30.4	35.8	1.9881	0.331350
129.9	12.9	0.0297	0.004948

the 17° angular difference in fold axis orientation led to the rejection of cylindricity in the area as a whole.

With the rejection of the East Pit as a domain it became neccesary to test whether or not the two halves could be considered domains in which folding was cylindrical. The above procedures were applied to those values given below. Neither null hypothesis could be rejected and thus folding was considered cylindrical in both areas.

(d) Run Commands, Sample Input and Output for the Program SECT5 available in the Deptment of Geology

RUN SEQUENCE

```
#$r [illegible]sect5[illegible]plot[illegible]  [illegible]  *print* 8-*print* 2[illegible]b
#15:23:1[illegible]
 *PRINT* ASSIGNED RECEIPT NUMBER [illegible]641
        1.
     123.      30.       0.       0.       0.    1[illegible].      30.
 *[illegible]*9
 *PRINT* [illegible]641 RELEASED, [illegible]
#15:24:3[illegible]
#$run *calcomp[illegible]file[illegible] b
#15:26:1[illegible]
 FILE  B
 LENGTH  24.0 IN.   APPROX TIME   [illegible]   APPROX COST $  0.[illegible]
 DO YOU STILL WANT THIS PLOT OUTPUT [illegible] OR N)
 y
 B RENAMED TO PLOT0002
 [illegible]
#15:[illegible] .192 [illegible] 0
```

Input

MELF MESOSCOPIC STUDY ([illegible])
INPUT DATA:

STA	ID	X	Y	Z	DATA	
1	2	47	-66	4	50	71
2	2	26	-65	16	45	74
3	2	5	-41	4	52	69
4	2	-21	-22	4	45	75
5	2	-42	-4	13	44	83
6	2	-67	17	23	40	68
7	2	-88	29	35	42	73
8	2	-64	72	22	180	53
9	2	-25	61	15	195	49
10	1	13	58	14	[illegible]	34
11	1	7	81	27	188	47
12	2	2	93	36	166	32
51	5	402	-342	-77	37	60
52	3	301	-437	-30	160	48
53	4	347	-546	-42	154	35
54	4	406	-505	-71	155	30
55	5	348	-509	-69		
56	3	272	-209	-50		
57	3	357	-365	-92		

Output

NSTA	X	Y	PITCH	ID	L	M	N
1	43.5	47.4	113.9	2	-0.4043	0.9133	-0.0491
2	38.3	43.1	108.8	2	-0.3222	0.9467	-0.0067
3	30.7	17.3	116.6	2	-0.4466	0.8928	-0.0572
4	30.1	1.2	104.5	2	-0.2505	0.9667	-0.0522
5	27.4	-4.8	100.6	2	-0.1832	0.9803	-0.0735
6	24.5	-12.4	111.6	2	-0.3648	0.9237	0.1173
7	26.7	-14.0	108.2	2	-0.3115	0.9492	0.0453
8	-22.3	-27.6	41.1	2	-0.7502	-0.6542	-0.0958
9	-35.6	-14.7	45.5	2	-0.6972	-0.7092	0.1045
10	-55.0	0.8	27.5	1	-0.8783	-0.4581	0.1367
11	-70.4	3.0	40.7	1	-0.7566	-0.6516	0.0535
12	-77.3	5.3	20.4	2	-0.9344	-0.3477	0.0777
51	49.6	196.0	99.7	5	-0.1676	0.9842	0.0571
52	185.3	222.6	25.7	3	-0.8839	-0.4263	-0.1926
53	248.2	262.3	16.2	4	-0.9602	-0.2781	-0.0249
54	186.8	249.6	14.5	4	-0.9665	-0.2500	0.0580
55	168.7	249.2	61.9	5	0.0000	0.0000	-0.0000
56	15.2	128.0	61.9	3	0.0000	0.0000	-0.0000
57	92.6	170.6	61.9	3	0.0000	0.0000	-0.0000

Profile

ORIENTATION OF FOLD AXIS IS 125.0 30.0
COORDINATES OF PROFILE ORIGIN ARE 0.0 0.0 0.0
PROFILE LOOKING IN DIRECTION 125.0 30.0



MPEP MESOSCOPIC STUDY (ROTATED)

(e) Run Commands, Sample Input and Resulting Output for the Program DOMROT available in the Department of Geology

```
#r hakc:domrot [illegible] 2=*print* 5=[illegible] 7=*print* 8=*print*
#15:11:[illegible]
*PRINT* ASSIGNED RECEIPT NUMBER 330637
    [illegible]    [illegible]    125.    -162.    [illegible]    125.    30.

 [illegible] ROTATION PROGRAM
[illegible]    128.0    [illegible]
TO BE ROTATED TO    [illegible]    [illegible]
ABOUT THE POINT    125.0    -162.0
 MPEP MESOSCOPIC STUDY (SOUTH)
125552222223345534453330
*PRINT* 330637 RELEASED, [illegible] PAGES
#17:17:[illegible] [illegible] RC=0
```

INPUT

MPEP MESOSCOPIC STUDY (SOUTH)
INPUT DATA:

STA	ID	X	Y	Z	DATA	
1	1	135	-183	-2	4[illegible]	59
2	2	162	-217	[illegible]	51	56
3	5	226	-162	3	51	56
4	5	266	-191	14	21[illegible]	88
5	5	299	-234	10	46	76
6	5	355	-285	11	213	78
7	2	2[illegible]1	-355	0	64	26
8	2	258	-344	-4	37	31
9	2	237	-299	-5	3[illegible]	44
10	2	205	-266	-5	45	56
11	2	1[illegible]3	-243	-3	52	53
12	2	319	-403	7	93	13
13	3	292	-439	43	77	31
14	3	409	-463	20	56	30
15	4	416	-438	18	51	50
16	5	429	-386	31	53	69
17	5	400	-360	16	37	81
18	3	285	-443	56	174	35
19	4	326	-553	73	173	21
20	5	383	-523	52		
21	4	392	-520	51	181	17
22	3	275	-222	-9		
23	3	357	-383	-5		
24	3	375	-443	-3		

OUTPUT

MPEP MESOSCOPIC STUDY (SOUTH)
ROTATED DATA:

STA	ID	X	Y	Z	DATA	
1	1	134	-1[illegible]1	-7	54	62
2	2	163	-213	-17	59	60
3	5	225	-156	-17	58	6[illegible]
4	5	267	-194	-20	216	[illegible]9
5	5	299	-223	-39	47	7[illegible]
6	5	356	-270	-5[illegible]	207	[illegible]1
7	2	283	-341	-67	84	35
8	2	259	-331	-64	60	73
9	2	237	-288	-52	52	45
10	2	205	-258	-40	53	58
11	2	184	-237	-29	60	57
12	2	323	-387	-77	111	27
13	3	305	-431	-43	90	42
14	3	415	-443	-94	76	37
15	4	420	-418	-93	61	54
16	5	435	-368	-73	56	73
17	5	402	-342	-77	37	90
18	3	301	-437	-30	160	48
19	4	347	-546	-42	154	35
21	4	406	-505	-71	155	30
20	5	398	-509	-69		
22	3	272	-209	-50		
23	3	357	-363	-97		
24	3	376	-421	-1[illegible]5		

(f) Mapping Subroutines BOUND, DRAW and MAP

```
C********SUBROUTINES TO PLOT ORIENTATION  SYMBOLS ON MAPS ********
C
C        THIS FILE CONTAINS THREE SUBROUTINES REQUIRED IN THE PLOTTING
C         OF MAPS.  MAP READS INPUT DATA AND CALLS SUBROUTINE DRAW TO
C          CONSTRUCT THE ORIENTATION SYMBOLS.  DRAW CONSTRUCTS THE
C           ORIENIATION SYMBOLS WHILE BOUND IS USED TO PUT A BOUNDARY
C            AROUND THE ENTIRE MAP.
C
      SUBROUTINE BOUND(A,B,C,D,E,F)
C******  DESIGNED TO DRAW A BOUNDARY AROUND A MAP
C          LABELS BEING ON BASE AND LEFT HAND AXIS.
C  A=XLENGTH
C  B=YLENGTH
C  C=X LABEL
C  D=Y LABEL
C  E=UNIT INCREMENT PER VIRTUAL UNIT
C  F=TIC SPACING
      G=A+1.
      H=B+1.
      CALL AX2EP(F,1,-1)
      CALL AXIS2(1.,1.,' ',-1,A,0.,C,E,F)
      CALL AXIS2(1.,1.,' ',1,B,90.,D,E,-F)
      CALL AXIS2(1.,H,' ',-1,-A,0.,C,E,F)
      CALL AXIS2(G,1.,' ',1,-B,90.,D,E,F)
      RETURN
      END
C**************SUBROUTINE DRAW ******************
      SUBROUTINE DRAW(X,Y,N,HT,DD,DI)
      INTEGER N
      REAL DD,DI,DDD,Z,W,V
      REAL X,Y,S,HT,K,KK,P,Q
      IF(N .EQ. 0)GO TO 30
C*******CHECK IF BEDS OVERTURNED, IF SO ADD 180 TO DIP-DIRECTION
       IF(DI .LE. 90.0)  GO TO 15
       DDD=DD+180.
       IF(DDD .LE. 360.)  GO TO 3
       DDD=DDD-360.
       W=ABS(DDD-450.)
       GO TO 6
3      W=ABS(DDD-450.)
6      G=W+90.0
       H=W+270.
       R=HT/4.
      DD=DDD
C*******CONVERT DEGREES TO RADIANS
15     Z=DD*1.745329E-2
      U=(DD+180.)*1.745329E-2
       V=(DD+90.0)*1.745329E-2
       K=(DD-90.0)*1.745329E-2
      IF(DI .LE. 90.0)  GO TO 20
C****** COORDINATE CALCS. FOR  OVERTURNED CIRCLE SYMBOL AND ITS PLOTTING
      X1=X+SIN(U)*(HT*.33)
      Y1=Y+COS(U)*(HT*.33)
      X2=X+SIN(V)*(HT*.5)
      Y2=Y+COS(V)*(HT*.5)
      X3=X2+SIN(U)*(HT*.33)
      Y3=Y2+COS(U)*(HT*.33)
      CALL PLOT(X,Y,3)
      CALL PLOT(X1,Y1,2)
      CALL CIRCLE(X1,Y1,G,H,R,R,0.0)
      CALL PLOT(X3,Y3,3)
      CALL PLOT(X2,Y2,2)
      DI=180.-DI
C**********DETERMINE COORDINATES FOR SYMBOL
20     E=X+SIN(Z)*(HT*.66)
       F=Y+COS(Z)*(HT*.66)
       A=X+SIN(V)*HT
       B=Y+COS(V)*HT
       C=X+SIN(K)*HT
       D=Y+COS(K)*HT
C********PLOT SYMBOL ***********
      CALL PLOT(E,F,3)
      CALL PLOT(X,Y,2)
      CALL PLOT(A,B,3)
      CALL PLOT(C,D,2)
      Q=Y-(2.5*HT)
      CALL NUMBER(X,Q,HT,DI,0.0,-1)
30    RETURN
      END
C*****  READ DATA AND PLOT SYMBOLS *******
      SUBROUTINE MAP(A,B,D,E)
      INTEGER C,BLANK/' '/,X,Y,DD,DI
      N=1
      DO 1 I=1,500
      READ(5,10,END=9)X,Y,DD,DI,C
      IF(C .EQ. BLANK)  GO TO 2
      DI=90-DI+90
      DD=DD+180
      IF(DD .GT. 360)  DD=DD-360
2     XX=(X+A)/D+1.
      YY=(Y+B)/D+1.
      IF(DD .EQ. 0)  GO TO 3
      DDD=DD
      DID=DI
      CALL DRAW(XX,YY,N,E,DDD,DID)
      GO TO 1
3     CALL SYMBOL(XX,YY,E,003,0.0,-1)
1     CONTINUE
10    FORMAT(1X,2(I5),6X,2I3,1X,A1)
9     RETURN
      END
```

Example of Map Production

```
#cr -file
# FILE "-FILE" HAS BEEN CREATED.
#number
#      1_       call plots
#      2_       call bound(7.,8.,-2.,-6.,1.,2.)
#      3_       call map(-200.,-600.,100.,.1)
#      4_       call plots(0.0,0.0,999)
#      5_       stop
#      6_       end
#      7_#unnumber
#  *forts scards=-file
#15:13:24
 MAIN        NO ERRORS
#15:13:26  .113 RC=0
#r -load#+bankc+*plotlib 5=ep(2,59) 9=-map
#15:19:08
#15:19:10  .145 RC=0
#r *calcompq par=file=-map
#15:19:27
 FILE=-MAP
 LENGTH= 19.5 IN.   APPROX TIME=    64. SECS.   APPROX COST=$   0.37
 DO YOU STILL WANT THIS PLOT QUEUED? (Y OR N)
```



(g) Run Commands and Sample Output for the Programs STEREO, FINPUT and PLOT available in the Department of Geology

```
#$RUN STEREO 5=DOMAIN1 6=-DATA
#21:30:55
#21:30:57  T=.202  RC=0
#$SOURCE HAKC:FINPUT
#$CR -OD1 TYPE=SEQ SIZE=10P
# FILE "-OD1" HAS BEEN CREATED.
#$CR -OD2 TYPE=SEQ SIZE=10P
# FILE "-OD2" HAS BEEN CREATED.
#$R HAKC:FINPUT(100)+HAKC:ODPROLIB 1=-DATA 5=*MSOURCE* 6=*SINK* 7=-OD1 9=-SCR
#21:31:16
  DOMAIN 1
#21:31:21  T=1.045  RC=0
#$COPY -OD1 -OD2
#$SOURCE HAKC:PLOT
#$R *SOURCE*+HAKC:ODPROLIB 1=-OD2 5=*MSOURCE* 6=*SINK* 9=-SCR
#21:31:33
 TO SKIP TO NEXT DATA SET ENTER A BLANK LINE
 TO TERMINATE ENTER '?'
  DOMAIN 1
   55 POINTS
 ENTER PERCENT SIZE OF COUNTING CIRCLE
 1


  DOMAIN 1
  PERCENT OF  55 POINTS IN  1.0 PERCENT OF AREA OF HEMISPHERE
 EQUAL-AREA PROJECTION; FRACTIONS TRUNCATED
                                        0   0   0   0   0

                                0   0   0   0   0   0   0   0   0
                            0                                       0

                        0   0   0   0   0   0   0   0   0   0   0   0   0
                     0                                                     0

                    0   0   0   0   0   0   0   1   3   5   5   1   0   0   0
                 0                                                            0

                0   0   0   0   0   0   0   1   9  16  16   5   1   0   0   0   0
              0                                                                  0

            0   0   0   0   0   0   0   0   3  10  16  10   3   1   0   0   0   0   0

            0   0   0   0   0   0   0   1   9   7   7   3   0   0   0   0   0   0   0
          0                                                                            0

            0   0   0   0   0   3   9  16  10   3   0   0   0   0   0   0   0   0   0
         0                                                                               0

         0  0   0   0   0   0   7   7   9   1   0   0   0   0   0   0   0   0   0   0   0

         0                                                                               0
            0   0   0   0   1   5   3   0   0   0   0   0   0   0   0   0   0   0   0

          0                                                                            0
            0   0   0   1   1   3   1   1   0   0   0   0   0   0   0   0   0   0   0

            0   0   0   1   1   0   0   0   0   0   0   0   0   0   0   0   0   0   0

              0                                                                  0
                0   0   1   1   0   0   0   0   0   0   0   0   0   0   0   0   0

                 0                                                            0
                    0   0   0   0   0   0   0   0   0   0   0   0   0   0   0

                     0                                                     0
                        0   0   0   0   0   0   0   0   0   0   0   0   0

                            0                                       0
                                0   0   0   0   0   0   0   0   0

                                        0   0   0   0   0
```

(h) Run Commands and the APL Program THICK Used to Calculate the Thickness of Strata Between Two Outcrops Whose Coordinates and Bedding Orientations are Known

```
      [illegible] 1771 [illegible] 32 THICK [illegible]174 3836 [illegible] 187 37
FOLD-AXIS :  [illegible] [illegible]
THICKNESS:   [illegible]

      [illegible] [illegible]157 [illegible] 5791 105 [illegible] THICK [illegible] [illegible] [illegible] 21
THICKNESS:   373.3

      ∇THICK[⎕]∇
    ∇ TH←G THICK [illegible];LM;[illegible];LMN;TP;RM;W;[illegible]IT;[illegible];INT;L1;L2;X;Z;NPT
[1]   [illegible]
[2]   [illegible] 2 0 [illegible] [illegible](R[illegible]+.E[illegible]9)[illegible]
[3]   [illegible]
[4]   [illegible]TRND LMN[1]);[illegible]LMN[3]
[5]   RM [illegible] 1 0 [illegible](TP[1]+90)[illegible]TP[1];(TP[2]-90),TP
[6]   XYZ←[illegible](R[2] Q[2]),(R[1]-Q[1]),-R[3]-Q[3]
[7]   W←RM+.×DC
[8]   MC←[illegible] 2 [illegible](2×NPT),1○NPT+(PI÷2)+PIT+2×PI×0[illegible]PIT+[illegible]3○W[1;]÷W[2;]+1E¯7
[9]   [illegible]0,MC[2;]+.×XYZ 2 1 [illegible]
[10]  INT←[illegible]MC
[11]  L1←[illegible]INT*2)*0.5
[12]  TH←L1-L2←([illegible]INT XYZ 2 1 3)*2)*0.5.
[13]  'FOLD-AXIS : ',[illegible]TP
[14]  [illegible]
[15]  TH←[illegible][2] Q[2]),(R[1] Q[1]),(-R[3]-Q[3]))+.×DC← 2 0 [illegible] [illegible] 4 5 [illegible]
[16]  'THICKNESS: ',[illegible] TH
```

APPENDIX 4

Domain Plots

K=Carduim
B=Blackstone
M=Mountain Park
L=Luscar
1=Kennedy Seam
2=Kennedy Seam
C=Cadomin
N=Nikanassin
F=Fernie
P=pre-Jurassic



*10²
-345.00 -330.00 -315.00 -300.00 -285.00 -270.00 -255.00 -240.00 -225.00 -210.00 -195.00
140.00 125.00 110.00 95.00 80.00 65.00 50.00 35.00 20.00 5.00 -10.00
Y-AXIS
*10²
X-AXIS
*10²

DOMAIN 1


*10¹
-2600.00 -2550.00 -2500.00 -2450.00 -2400.00 -2350.00 -2300.00 -2250.00 -2200.00 -2150.00 -2100.00
995.00 945.00 895.00 845.00 795.00 745.00 695.00 645.00 595.00 545.00 495.00
Y-AXIS *10¹
X-AXIS *10¹

DOMAIN 2



*10¹
-2020.00
-2000.00
-1980.00
-1960.00
-1940.00
-1920.00
-1900.00
-1880.00
-1860.00
-1840.00
-1820.00
X-AXIS
*10¹
Y-AXIS
*10¹
231.00
251.00
271.00
291.00
311.00
331.00
351.00
371.00
391.00
411.00
431.00

DOMAIN 3


*10¹
-1750.00 -1700.00 -1650.00 -1600.00 -1550.00 -1500.00 -1450.00 -1400.00 -1350.00 -1300.00 -1250.00
470.00 420.00 370.00 320.00 270.00 220.00 170.00 120.00 70.00 20.00 -30.00
Y-AXIS *10¹
X-AXIS *10¹

DOMAIN 4


*10¹
-4050.00 -4000.00 -3950.00 -3900.00 -3850.00 -3800.00 -3750.00 -3700.00 -3650.00 -3600.00 -3550.00
X-AXIS *10¹
Y-AXIS *10¹
180.00 230.00 280.00 330.00 380.00 430.00 480.00 530.00 580.00 630.00 680.00

DOMAIN 5


*10¹
-3550.00
-3500.00
-3450.00
-3400.00
-3350.00
-3300.00
-3250.00
-3200.00
-3150.00
-3100.00
-3050.00
1020.00
970.00
920.00
870.00
820.00
770.00
720.00
670.00
620.00
570.00
520.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 5(A)


*10^1
2450.00 2520.00 2590.00 2660.00 2730.00 2800.00 2870.00 2940.00 3010.00 3080.00 3150.00
1210.00 1140.00 1070.00 1000.00 930.00 860.00 790.00 720.00 650.00 580.00 510.00
Y-AXIS
X-AXIS

DOMAIN 6



DOMAIN 7


*10¹
630.00
660.00
690.00
720.00
750.00
780.00
810.00
840.00
870.00
900.00
930.00
-135.00
-165.00
-195.00
-225.00
-255.00
-285.00
-315.00
-345.00
-375.00
-405.00
-435.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 8



*10²
-400.00 -390.00 -380.00 -370.00 -360.00 -350.00 -340.00 -330.00 -320.00 -310.00 -300.00
139.00 129.00 119.00 109.00 99.00 89.00 79.00 69.00 59.00 49.00 39.00
Y-AXIS *10²
X-AXIS *10²

DOMAIN 9


*10¹
-3540.00
-3520.00
-3500.00
-3480.00
-3460.00
-3440.00
-3420.00
-3400.00
-3380.00
-3360.00
-3340.00
800.00
780.00
760.00
740.00
720.00
700.00
680.00
660.00
640.00
620.00
600.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 10



*10¹
-3420.00
-3390.00
-3360.00
-3330.00
-3300.00
-3270.00
-3240.00
-3210.00
-3180.00
-3150.00
-3120.00
780.00
750.00
720.00
690.00
660.00
630.00
600.00
570.00
540.00
510.00
480.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 11



*10¹
-3220.00 -3150.00 -3080.00 -3010.00 -2940.00 -2870.00 -2800.00 -2730.00 -2660.00 -2590.00 -2520.00
1240.00 1170.00 1100.00 1030.00 960.00 890.00 820.00 750.00 680.00 610.00 540.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 12


*10²
-310.00
-300.00
-290.00
-280.00
-270.00
-260.00
-250.00
-240.00
-230.00
-220.00
-210.00
0.00
10.00
20.00
30.00
40.00
50.00
60.00
70.00
80.00
90.00
100.00
Y-AXIS *10²
X-AXIS *10²

DOMAIN 13


*10¹
-4410.00
-4340.00
-4270.00
-4200.00
-4130.00
-4060.00
-3990.00
-3920.00
-3850.00
-3780.00
X-AXIS
*10¹
1400.00
1330.00
1260.00
1190.00
1120.00
1050.00
980.00
910.00
840.00
770.00
700.00
*10¹

DOMAIN 14



*10¹
-4600.00 -4550.00 -4500.00 -4450.00 -4400.00 -4350.00 -4300.00 -4250.00 -4200.00 -4150.00 -4100.00
860.00 810.00 760.00 710.00 660.00 610.00 560.00 510.00 460.00 410.00 360.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 15



*10¹
-4620.00
-4550.00
-4480.00
-4410.00
-4340.00
-4270.00
-4200.00
-4130.00
-4060.00
-3990.00
-3920.00
1645.00
1575.00
1505.00
1435.00
1365.00
1295.00
1225.00
1155.00
1085.00
1015.00
945.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 16


*10¹
-5100.00
-5050.00
-5000.00
-4950.00
-4900.00
-4850.00
-4800.00
-4750.00
-4700.00
-4650.00
-4600.00
1382.00
1332.00
1282.00
1232.00
1182.00
1132.00
1082.00
1032.00
982.00
932.00
882.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 17


*10'
-3850.00
-3780.00
-3710.00
-3640.00
-3570.00
-3500.00
-3430.00
-3360.00
-3290.00
-3220.00
-3150.00
X-AXIS
*10'
Y-AXIS
*10'
630.00
700.00
770.00
840.00
910.00
980.00
1050.00
1120.00
1190.00
1260.00
1330.00
*10'

DOMAIN 18


*10¹
-3300.00 -3270.00 -3240.00 -3210.00 -3180.00 -3150.00 -3120.00 -3090.00 -3060.00 -3030.00 -3000.00
Y-AXIS
*10¹
800.00 830.00 860.00 890.00 920.00 950.00 980.00 1010.00 1040.00 1070.00 1100.00
X-AXIS

DOMAIN 19



*10¹
-3900.00 -3850.00 -3800.00 -3750.00 -3700.00 -3650.00 -3600.00 -3550.00 -3500.00 -3450.00 -3400.00
1240.00 1190.00 1140.00 1090.00 1040.00 990.00 940.00 890.00 840.00 790.00 740.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 20


*10¹
-1380.00 -1350.00 -1320.00 -1290.00 -1260.00 -1230.00 -1200.00 -1170.00 -1140.00 -1110.00 -1080.00
-450.00 -480.00 -510.00 -540.00 -570.00 -600.00 -630.00 -660.00 -690.00 -720.00 -750.00
Y-AXIS
X-AXIS

DOMAIN 21


*10¹
-4050.00 -4000.00 -3950.00 -3900.00 -3850.00 -3800.00 -3750.00 -3700.00 -3650.00 -3600.00 -3550.00
700.00 750.00 800.00 850.00 900.00 950.00 1000.00 1050.00 1100.00 1150.00 1200.00
Y-AXIS *10¹
X-AXIS *10¹

DOMAIN 22



*10¹
-3390.00 -3360.00 -3330.00 -3300.00 -3270.00 -3240.00 -3210.00 -3180.00 -3150.00 -3120.00 -3090.00
1365.00 1335.00 1305.00 1275.00 1245.00 1215.00 1185.00 1155.00 1125.00 1095.00 1065.00
Y-AXIS *10¹
X-AXIS *10¹

DOMAIN 23



X-AXIS
Y-AXIS
*10^1
-4000.00 -3950.00 -3900.00 -3850.00 -3800.00 -3750.00 -3700.00 -3650.00 -3600.00 -3550.00 -3500.00
750.00 800.00 850.00 900.00 950.00 1000.00 1050.00 1100.00 1150.00 1200.00 1250.00

DOMAIN 24


*10²
-343.00 -333.00 -323.00 -313.00 -303.00 -293.00 -283.00 -273.00 -263.00 -253.00 -243.00
Y-AXIS
*10²
50.00 60.00 70.00 80.00 90.00 100.00 110.00 120.00 130.00 140.00 150.00
X-AXIS
*10²

DOMAIN 25



*10'
-5040.00 -4970.00 -4900.00 -4830.00 -4760.00 -4690.00 -4620.00 -4550.00 -4480.00 -4410.00 -4340.00
870.00 940.00 1010.00 1080.00 1150.00 1220.00 1290.00 1360.00 1430.00 1500.00 1570.00
Y-AXIS *10'
X-AXIS *10'

DOMAIN 28



*10²
-570.00
-560.00
-550.00
-540.00
-530.00
-520.00
-510.00
-500.00
-490.00
-480.00
-470.00
50.00
60.00
70.00
80.00
90.00
100.00
110.00
120.00
130.00
140.00
150.00
Y-AXIS
*10²
X-AXIS
*10²

DOMAIN 29



*10¹
3680.00
3710.00
3740.00
3770.00
3800.00
3830.00
3860.00
3890.00
3920.00
3950.00
3980.00
-450.00
-480.00
-510.00
-540.00
-570.00
-600.00
-630.00
-660.00
-690.00
-720.00
-750.00
Y-AXIS
*10¹
X-AXIS
*10¹

DOMAIN 30

*10'
-5740.00 -5670.00 -5600.00 -5530.00 -5460.00 -5390.00 -5320.00 -5250.00 -5180.00 -5110.00 -5040.00
600.00 670.00 740.00 810.00 880.00 950.00 1020.00 1090.00 1160.00 1230.00 1300.00
Y-AXIS
*10'
X-AXIS
*10'

DOMAIN 31


*10²
-600.00
-550.00
-500.00
-450.00
-400.00
-350.00
-300.00
-250.00
-200.00
-150.00
-100.00
540.00
490.00
440.00
390.00
340.00
290.00
240.00
190.00
140.00
90.00
40.00
Y-AXIS
*10²
X-AXIS
*10²

DOMAIN 34

APPENDIX 5

Stratigraphic Section Though Part of the Luscar Formation at the Northern end of the West Pit at Mountain Park

Luscar Formation in West Pit

UNIT NO.		Thickness	HEIGHT ABOVE BASE (METERS)
26	Coal seam (Kennedy)..........	5.4	84.7
25	Covered......................	6.2	79.3
24	Light grey sandstone, very soft due to weathering.......	4.6	73.1
23	Light grey, massive sandstone Trace of Lower Drummond Creek thrust.	4.9	68.5
22	Coal.........................	0.7	63.6
21	Green mudstone with ironstone concretions up to 0.3 m in diameter....................	3.9	62.9
20	Ironstone, ...	0.1	59.0
19	Coaly shale..................	0.1	58.9
18	Olive green mudstone with ironstones..................	1.4	58.8
17	Shaly coal...................	0.5	57.4
16	Grey mudstone................	0.2	56.9
15	Olive green, shaly mudstone, recessive, large ironstone concretions up to 12 cm in diameter....................	4.6	56.7
14	Brown, green and grey shales, thinnly bedded with iron stains and ironstones.......	4.3	52.1
13	Coal.........................	0.2	47.8

UNIT NO.		THICKNESS	HEIGHT ABOVE BASE (METERS)
12	Grey to brown mudstone.......	0.2	47.6
11	Coal.........................	0.1	47.4
10	Black and brown silty shale with ironstone concretions along bedding.................	5.8	47.3
9	Grey and brown siltstone platy weathering with cross bedding.................	17.6	41.5
8	Black shale grading to grey shale at top..................	2.2	23.9
7	Grey shale, occasional iron-stone bed to 5 cm............	5.3	21.7
6	Grey-brown siltstone, red weathering..................	1.3	16.4
5	Light brown to grey shaly mudstone.....................	1.4	15.1
4	Coal. (Kennedy)...............	12.7	13.7
3	Sandstone....................	0.3	1.0
2	Coal.........................	0.7	0.7
1	Sandstone....................	0.0	0.0



Geology of the Mountain Park Area
LEGEND
FORMATION BOUNDARY
KENNEDY SEAM
THRUST FAULT
NORMAL FAULT
SYNCLINE
ANTICLINE
OVERTURNED SYNCLINE
OVERTURNED ANTICLINE
BEDDING ORIENTATION
OVERTURNED BEDDING
ROAD 2 WHEEL DRIVE
ROAD 4 WHEEL DRIVE
WAPIABI
CARDIUM
BLACKSTONE
MOUNTAIN PARK
LUSCAR
CADOMIN
NIKANASSIN
FERNIE GROUP
PRE-JURASSIC UNIT
Kilometers
SCALE 1:25 000
NORTH
WHITEHORSE CREEK
DRUMMOND CREEK
PROSPECT CREEK
McLEOD RIVER
CADOMIN MOUNTAIN SYNCLINE
CADOMIN MOUNTAIN ANTICLINE
KRYCZKA THRUST
McKENZIE CREEK THRUST
HARRIS CREEK
HARRIS CREEK ANTICLINE
HARRIS CREEK THRUST
SYNCLINE
DRUMMOND CREEK SYNCLINE
LOWER DRUMMOND CREEK THRUST
UPPER DRUMMOND CREEK THRUST
DRUMMOND CREEK ANTICLINE
PROSPECT CREEK THRUST
HARRIS MOUNTAIN ANTICLINE
HARRIS MTN. SYNCLINE
WEST PIT
SYNCLINE PIT
MOUNTAIN PARK
EAST PIT
HARRIS MTN.
EAST PROSPECT CREEK
CHEVIOT CREEK
THORNTON CREEK SYNCLINE
THORNTON CREEK
SYNCLINE THRUST
McCONNELL THRUST
McKENZIE CREEK